

STADIUM RENOVATIONS COUNTYWIDE

Background

This contract is part of an ongoing effort in the County to replace the grass fields at the High Schools with artificial/safety turf.

The field is located on the inside of a track. There are also track and field elements such as long jump ,high jump and pole vault runways and pits. The construction elements consist of removal of existing grass and soil, installation of a perimeter concrete curb, installation of field drainage system, installation of the Turf system that consists of artificial turf that will be underlain by 18 inches of graded aggregate. The Turf fibers are 2 1/2 inches in height and the first 1 1/4 inches is filled with a sand and rubber mix.

Benefits

- Improved, reliable and safe playing surface
- Reduced lost days, cancellations, and postponements due to adverse weather
- Reduced maintenance, mowing, irrigation, seeding
- Positive drainage

Project Information

Project Manager	Ken Dinnis (410) 222-7559
Design Consultant	Am Dyne Corporation
Contractor	Sunny Acres Sports Systems
Inspection Manager	Dewberry

For more information contact Customer Relations at 410-222-7582 or email us at customer@aacounty.org

<u>Field</u>	<u>Construction Start</u>	<u>Completion Date</u>	<u>Estimated Total Project Cost</u>
Arundel High School	May 2008	August 2008	\$870.5K
Annapolis High School	May 2008	August 2008	\$888.7K
Chesapeake High School	October 2010	May 2010	\$809.5K
Old Mill High School	November 2010	May 2010	\$830.3K



Chesapeake High School



Old Mill High School