

**SECTION 01420**

**TEMPORARY RAISED PAVEMENT MARKERS  
FOR MAINTENANCE OF TRAFFIC**

**01420.01 GENERAL**

**A. Description**

This work shall consist of furnishing and installing, complete in place, temporary raised pavement markers as indicated on the approved Traffic Control Plan or as directed by the Engineer.

**B. Related Work Included Elsewhere**

Traffic control plan; Section 01411.

**C. Quality Assurance**

The Engineer will inspect all materials before and/or after installation to ensure compliance with the Contract Documents.

**D. SUBMITTALS**

Shop drawings shall be submitted as specified in the "General Provisions" for all raised pavement markers furnished giving general product information and installation instructions.

**01420.02 MATERIALS**

**A. Materials Furnished by the County**

The County will not furnish any materials for raised pavement marker installation.

**B. Contractor's Options**

Temporary raised pavement markers shall be the Stimsonite 88 Catadots, Safety Guide Markers, Ray-0-Lite Markers, or approved equal.

**01420.03 EXECUTION**

All materials, equipment, and services necessary for the complete installation of the temporary raised pavement markers, as indicated on the approved Traffic Control Plan, shall be as prescribed by the manufacturer furnishing the material.

**01420.04 METHOD OF MEASUREMENT**

**A. Installation**

1. Measurement for temporary raised pavement marker installation will be made of the total number actually installed and accepted by the Engineer.
2. Should properly installed marker(s) be destroyed by traffic or snowplow operations, the replacement of each marker destroyed will be included in the measurement.

**B. Removal**

Measurement for removal of raised pavement markers will be made of the actual total number of pavement markers removed by the Contractor.

**01420.05 BASIS OF PAYMENT**

**A. Installation**

Payment for the installation of temporary pavement markers will be made at the price bid each for temporary raised pavement marker placed in accordance with the approved Traffic Control Plan or as directed by the Engineer. Payment will include furnishing all materials, labor, tools, equipment, and incidentals necessary to satisfactorily complete the work.

**B. Removal**

1. Payment for the removal of raised pavement markers will be made at the price bid each for the number directed to be removed by the Engineer. The price bid shall include furnishing all materials, labor, tools, equipment, and incidentals to satisfactorily complete the work.
2. All materials when satisfactorily removed from the project site shall become the property of the Contractor.