




## STA. 601+50 TO STA. 606+85 TYPICAL SECTION - STA. 604+00 NOT TO SCALE



### NON-ROOFTOP DISCONNECT NRD 7-1 STA. 606+85 TO STA. 611+00 TYPICAL SECTION - STA. 609+00 NOT TO SCALE



#### NON-ROOFTOP DISCONNECT NRD 11-1 STA. 300+30 TO STA. 304+90 TYPICAL SECTION - STA. 303+00 NOT TO SCALE




NON-ROOFTOP DISCONNECT NRD 12-1 STA. 306+40 TO STA. 319+00 TYPICAL SECTION - STA. 316+00 NOT TO SCALE

#### NON-ROOFTOP DISCONNECT NOTES:


- 1. ALL NON-ROOFTOP DISCONNECTIONS ARE FOR AREAS OF THE PROPOSED TRAIL THROUGH HIGHLY WOODED AND VEGETATIVE AREAS.
- 2. IN ORDER TO KEEP THE INTENT OF STORMWATER MANAGEMENT, NO ADDITIONAL TREE CLEARING WILL BE PERFORMED FOR IMPLEMENTATION OF MICRO-SCALE OR STRUCTURAL PRACTICES IN THE STATION LIMITS OF NON-ROOFTOP DISCONNECTIONS.
- 3. THE AREAS RECEIVING NON-ROOFTOP DISCONNECT AS SHOWN IN THE TYPICAL SECTIONS ABOVE SHALL REMAIN UNDISTURBED. NO SLOPES >5% ARE ANTICIPATED WITHIN THE DISCONNECTION ZONES OFF OF THE PROPOSED TRAIL.
- 4. AREAS RECEIVING DISCONNECTED RUNOFF SHALL MINIMIZE DISTURBANCE AND COMPACTION. CONSTRUCTION VEHICLES AND EQUIPMENT SHALL AVOID THESE AREAS.
- 5. SHOULD AREAS RECEIVING DISCONNECTED RUNOFF BECOME COMPACTED, SCARIFYING THE SURFACE OR ROTOTILIING THE SOIL TO A DEPTH OF FOUR INCHES SHALL BE PERFORMED TO ENSURE PERMEABILITY AND DONE AT THE CONTRACTOR'S EXPENSE.
- 6. FINAL INSPECTION SHALL BE CONDUCTED AT THE END OF CONSTRUCTION TO ENSURE THAT ADEQUATE TREATMENT AREAS AND PERMANENT STABILIZATION HAS BEEN ESTABLISHED.
- 7. AREAS RECEIVING DISCONNECTED RUNOFF SHALL BE PROTECTED FROM FUTURE COMPACTION.

## B/L CONSTRUCTION -SANDY POINT STATE PARK TRAIL 01 PROPOSED-GRADE 10' TRAIL 10' NON-ROOFTOP DISCONNECTION EX. GROUND


#### NON-ROOFTOP DISCONNECT NRD 14-1 STA. 321+65 TO STA. 334+40 TYPICAL SECTION - STA. 333+00 NOT TO SCALE




#### NON-ROOFTOP DISCONNECT NRD 14-2 STA. 500+75 TO STA. 506+85 TYPICAL SECTION - STA. 503+25 NOT TO SCALE



#### NON-ROOFTOP DISCONNECT NRD 15-1 STA. 334+40 TO STA. 338+60 TYPICAL SECTION - STA. 336+00 NOT TO SCALE




NON-ROOFTOP DISCONNECT NRD 15-2 STA. 340+40 TO STA. 342+52 TYPICAL SECTION - STA. 342+25 NOT TO SCALE




**Published: 01/01 Revised:** 

NOTE: TRASH RACK FROM AA COUNTY WATER QUALITY INLET (AACO STD. D/89) TO BE ADAPTED ON OPENING OF TYPE D INLET. SHOP DRAWING OF TRASH RACK AND INLET SHALL BE SUBMITTED FOR APPROVAL BY ENGINEER.



Published: 01/01 Revised:



	31 // 332313331	SW-08
ΛΤ	BROADNECK PENINSUL PHASE IB & V	A TRAIL

4 NORTH PARK DRIVE HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818



PROFESSIONAL CERTIFICATION

"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY

ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER

THE LAWS OF THE STATE OF

MD LICENSE NUMBER: 53587

EXPIRATION DATE: 12-09-2024

MARYLAND."

												500-08
Y.,.		REVISIONS						ANNE ARUNI	DEL COUNTY			
WILLIAM STATE OF THE STATE OF T	NO.	DESCRIPTION	BY	DATE			[	DEPARTMENT OF	PUBLIC WO	RKS		
3					APPROVED	DATE	APPROVED	DATE	SCALE: AS NOT	ED	BROADNECK PENINSUL	 _A TRAIL
~					Docusigned by:	11/20/2023   08:5	9 EST Juli Autus	11/17/2023   08:	DRAWN BY:	DMT	PHASE IB & V	
WEER					CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT		
William .					APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>60</u> OF 116	STORMWATER MANA	AGEMEN <sup>®</sup>
					DocuSigned by:  **David C. Braun**	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:	PROJECT NO.	P504100	PLAN	
/2023					ASSISTANT CHIEF EN	NGINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	. P504105		

#### **GRASS SWALE ESD-1-1** SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

SWM FACILITY NUMBER	MDE/PRD NUMBER	SHA CONTRACT NUMBER
TBA	N/A	TRACKING NO. 20APAA014XX

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	2'		
TOTAL LENGTH (FT)	200'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	1.6%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION E ALSO PROVIDE COMPUTAT			
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	24.65 (MAX.)		
ESDv FLOW DEPTH (IN.)	1.80 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.29 FPS		
10-YR WATER SURFACE ELEVATION (FT)	25.09 (MAX)		
10-YR FLOW DEPTH (IN.)	7.1 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.63 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: $\square$ MDE $\square$ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

#### STORMWATER MANAGEMENT AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT FACILITY (FACILITIES) SHOWN ON THE PLANS AND INDIVIDUALLY IDENTIFIED BELOW HAS (HAVE) BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS INCLUDED UNDER THE MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVAL, EXCEPT AS NOTED IN GREEN ON THE "AS-BUILT" DRAWINGS. FURTHERMORE, THE GREEN-NOTED EXCEPTIONS DO NOT ADVERSELY AFFECT THE DESIGN AND/OR THE INTENDED PERFORMANCE OF THE FACILITY (FACILITIES).

ESD-1-1 (GRASS SWALE)	ESD-1-3 (SUBMERGED GRAVEL WETLAND)
ESD-1-2 (GRASS SWALE)	ESD-2-1 (GRASS SWALE)

EACH SWM FACILITY IS IDENTIFIED INDIVIDUALLY BY A U	JNIQUE SWM FACILITY
NUMBER	

Name (Printed)	Signature	
Maryland Registration Number	Date	

PROFESSIONAL CERTIFICATION. "I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. , EXPIRATION DATE

"CERTIFY" MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED ON SUFFICIENT AND APPROPRIATE ONSITE INSPECTIONS AND MATERIAL TESTS CONDUCTED DURING CONSTRUCTION. NOTE: AS-BUILT CHECKLISTS CONTAINED IN THE CONTRACT DRAWINGS SHALL

BE COMPLETED BY THE AS-BUILT INSPECTOR AND SUBMITTED TO THE SHA

ALONG WITH THIS CERTIFICATION.

## GRASS SWALE ESD-1-2

#### SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

**SWM FACILITY NUMBER** MDE/PRD NUMBER SHA CONTRACT NUMBER TRACKING NO. 20APAA014XX TBA

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	□ INSPECTION REPORT □ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	2'		
TOTAL LENGTH (FT)	100'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.5%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION BELOW WHEN TOLERANCES ARE NOT MET. ALSO PROVIDE COMPUTATIONS AND SWM REPORT REVISIONS.			
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	22.63 (MAX.)		
ESDv FLOW DEPTH (IN.)	1.60 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.16 FPS		
10-YR WATER SURFACE ELEVATION (FT)	23.62 (MAX)		
10-YR FLOW DEPTH (IN.)	13.4 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.53 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: ☐ MDE ☐ PRD
ACCEPTED BY:	DATE:

## SUBMERGED GRAVEL WETLAND ESD-1-3

#### SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-2 SUBMERGED GRAVEL WETLAND MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

MDE/PRD NUMBER SHA CONTRACT NUMBER TRACKING NO. 20APAA014XX

	ADDITIONAL SUPPORTING DOCUMENTATION	DATE(S) OF
ACTIVITY	(SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	□INSPECTION REPORT □PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	□INSPECTION REPORT □PHOTOGRAPHS	
OBSERVED INSTALLATION OF GEOTEXTILE AND VERIFIED INSTALLATION PERFORMED AS SPECIFIED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF NO. 57 AGGREGATE	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF SUB- DRAIN, VERIFIED TYPE IS PPWP OR CPP-S, AND HAS SLOTTED PERFORATIONS	□INSPECTION REPORT □ PHOTOGRAPHS PIPE TYPE: □ PPWP □ CPP-S	
OBSERVED INSTALLATION OF NO. 7 AGGREGATE	□INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF COARSE SAND	□INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF APPROVED BIORETENTION SOIL MIX (BSM)	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ MATERIAL APPROVAL FORM	
	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF SPECIFIED VEGETATION	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	
OBSERVED VEGETATION AND VERIFIED AT LEAST A 50% SURVIVIAL RATE, WITHIN SWM FACILITY, ONE YEAR AFTER INITIAL INSTALLATION	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
CELL 1 BOTTOM WIDTH (FT)	AVG. 50'		
CELL 1 BOTTOM LENGTH (FT)	AVG. 30'		
CELL 1 LEFT SIDE SLOPE (H:V) – CANNOT BE STEEPER THAN 3:1	3:1		
CELL 1 RIGHT SIDE SLOPE (H:V) – CANNOT BE STEEPER THAN 3:1	3:1		
CELL 2 BOTTOM WIDTH (FT)	AVG. 40'		
CELL 2 BOTTOM LENGTH (FT)	AVG. 35'		
CELL 2 LEFT SIDE SLOPE (H:V) – CANNOT BE STEEPER THAN 3:1	3:1		
CELL 2 RIGHT SIDE SLOPE (H:V) – CANNOT BE STEEPER THAN 3:1	3:1		
SUB-DRAIN PIPE DIAMETER (IN.)	8 IN.		
SUB-DRAIN INVERT OUT ELEVATION (FT)	13.67		
INVERTED J-HOOK OUTLET ELEVATION (FT.) – CANNOT BE MORE THAN 4 IN. BELOW CELL BOTTOM ELEVATION AND NOT HIGHER THAN THE CELL BOTTOM ELEVATION	2" BELOW SURFACE BOTTOM		
THICKNESS OF NO. 57 AGGREGATE (IN.)	24"		
THICKNESS OF NO. 7 AGGREGATE (IN.) – MAY NOT BE LESS THAN 4 IN.	4 "		
THICKNESS OF COARSE SAND (IN.) – MAY NOT BE LESS THAN 4 IN.	4 "		
THICKNESS OF BSM (IN.) - MAY NOT BE LESS THAN 8 IN.	8 "		

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	18.00		
ESDv PONDING DEPTH (IN.) – MAY NOT EXCEED 12 IN.	12"		
2-YR WATER SURFACE ELEVATION (FT)	18.39		
10-YR WATER SURFACE ELEVATION (FT)	19.04		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 "		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: ☐ MDE ☐ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

# **GRASS SWALE ESD-2-1**

#### SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

SWM FACILITY NUMBER MDE/PRD NUMBER SHA CONTRACT NUMBER TRACKING NO. 20APAA014XX TBA N/A

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	2'		
TOTAL LENGTH (FT)	150'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.5%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION E ALSO PROVIDE COMPUTAT			
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	21.90 (MAX.)		
ESDv FLOW DEPTH (IN.)	1.20 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.14 FPS		
10-YR WATER SURFACE ELEVATION (FT)	22.38 (MAX)		
10-YR FLOW DEPTH (IN.)	7 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.28 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	N/A		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: ☐ MDE ☐ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

### STORMWATER MANAGEMENT NOTES:

- 1. CONSTRUCTION OF THE PROPOSED SHA BIORETENTION FACILITY WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 316 FOR 'STORMWATER MANAGEMENT (SWM) FILTRATION FACILITIES'.
- 2. ASBUILT CERTIFICATION WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 317 STORMWATER MANAGEMENT (SWM) FACILITY AS-BUILT CERTIFICATION.
- 3. UPON COMPLETION OF THE PROJECT, THE AS-BUILT CERTIFICATION MUST BE SIGNED; AND THE AS-BUILT PLANS (ALONG WITH THE FINAL STORMWATER MANAGEMENT REPORT) MUST BE ELECTRONICALLY FORWARDED TO MS. KIONA LEAH (KLEAH@MDOT.MARYLÁND.GOV). THIS WILL BE A CONDITION OF THE FINAL BOND.

NOTE: ANNE ARUNDEL COUNTY TO OWN, OPERATE AND MAINTAIN ESD 1-1, ESD 1-2, ESD 1-3, AND ESD 2-1


GP# G02018957


DWG. NO.: SW-09



REVISED 04-10-2018

4 NORTH PARK DRIVE HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818





REVISIONS	ANNE ARUI	NDEL COUNTY	
NO. DESCRIPTION BY DATE	DEPARTMENT OF PUBLIC WORKS		
	APPROVED DATE APPROVED DATE	SCALE: AS NOTED BROADNECK PENINSULA TRAIL	
	Docusigned by: 11/20/2023   08:59 EST ful Duty 11/17/2023   08	E: O DRAWN BY: DMT PHASE IB & V	
	CHIEF ENGINEER PROJECT MANAGER	CHECKED BY: DMT	
	APPROVED DATE APPROVED DATE	SHEET NO. 61_OF 116 STORMWATER MANAGEMEN	
	Docustigned by:    Darrid C. Braun	3:3 FROJECT NO. P504100 AS-BUILT	
3	ASSISTANT CHIEF ENGINEER CHIEF, RIGHT OF WAY	CONTRACT NO. P504105	

#### **GRASS SWALE ESD-3-1** SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

WM FACILITY NUMBER	MDE/PRD NUMBER	SHA CONTRACT NUMBER
TBA	N/A	TRACKING NO. 20APAA014XX

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	4'		
TOTAL LENGTH (FT)	900'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ALSO PROVIDE COMPUTAT	TIONS AND SW	M REPORT R	EVISIONS.
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	22.32 (MAX.)		
ESDv FLOW DEPTH (IN.)	3.8 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.22 FPS		
10-YR WATER SURFACE ELEVATION (FT)	23.16 (MAX)		
10-YR FLOW DEPTH (IN.)	13.9 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.45 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	N/A		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: $\square$ MDE $\square$ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

#### STORMWATER MANAGEMENT AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT FACILITY

(FACILITIES) SHOWN ON THE PLANS AND INDIVIDUALLY IDENTIFIED BELOW HAS (HAVE) BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS INCLUDED UNDER THE MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVAL, EXCEPT AS NOTED IN GREEN ON THE "AS-BUILT" DRAWINGS. FURTHERMORE, THE GREEN-NOTED EXCEPTIONS DO NOT ADVERSELY AFFECT THE DESIGN AND/OR THE INTENDED PERFORMANCE OF THE FACILITY (FACILITIES).

ESD-3-1 (GRASS SWALE)	ESD-4-1 (BIORETENTION)
ESD-3-2 (GRASS SWALE)	ESD-5-1 (GRASS SWALE)

EACH SWM FACILITY IS IDENTIFIED NUMBER	D INDIVIDUALLY BY A UNIQUE SWM FACILITY
Name (Printed)	Signature
Maryland Registration Number	Date

PROFESSIONAL CERTIFICATION. "I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. , EXPIRATION DATE

"CERTIFY" MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED ON SUFFICIENT AND APPROPRIATE ONSITE INSPECTIONS AND MATERIAL TESTS CONDUCTED DURING CONSTRUCTION. NOTE: AS-BUILT CHECKLISTS CONTAINED IN THE CONTRACT DRAWINGS SHALL BE COMPLETED BY THE AS-BUILT INSPECTOR AND SUBMITTED TO THE SHA

ALONG WITH THIS CERTIFICATION.

# GRASS SWALE ESD-3-2

MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

#### SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES

**SWM FACILITY NUMBER** MDE/PRD NUMBER SHA CONTRACT NUMBER TRACKING NO 20APAA014XX TBA

IDA	IN/A TRACKING N	U. 20APAA0 14X
ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	4'		
TOTAL LENGTH (FT)	800'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION BELOW WHEN TOLERANCES ARE NOT MET. ALSO PROVIDE COMPUTATIONS AND SWM REPORT REVISIONS.				
FEATURE	DESIGN	AS-BUILT	DIFFERENCE	
ESDv WATER SURFACE ELEVATION (FT)	20.83 (MAX.)			
ESDv FLOW DEPTH (IN.)	4.0 IN.			
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.23 FPS			
10-YR WATER SURFACE ELEVATION (FT)	21.48 (MAX)			
10-YR FLOW DEPTH (IN.)	11.7 IN.			
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.41 FPS			
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.			

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: ☐ MDE ☐ PRD
ACCEPTED BY:	DATE:

## **GRASS SWALE ESD-4-1**

#### SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES

SWM FACILITY NUMBER MDE/PRD NUMBER SHA CONTRACT NUMBER TBA TRACKING NO. 20APAA014XX N/A

MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	☐ INSPECTION REPORT ☐ PHOTOGRAPHS  RELEASE STRUCTURE: ☐ INLET ☐ WEIR ☐ CHECK DAM ☐ OUTFALL ☐ NOT APPLICABLE ☐ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	4'		
TOTAL LENGTH (FT)	320'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	2.8%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	21.68 (MAX.)		
ESDv FLOW DEPTH (IN.)	2.20 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.37 FPS		
10-YR WATER SURFACE ELEVATION (FT)	22.03 (MAX)		
10-YR FLOW DEPTH (IN.)	10.0 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.49 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	N/A		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY:   MDE   PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

#### **GRASS SWALE ESD-5-1** SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES

TBA

MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10. SWM FACILITY NUMBER MDE/PRD NUMBER SHA CONTRACT NUMBER

N/A

TRACKING NO. 20APAA014XX

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	8'		
TOTAL LENGTH (FT)	610'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION BELOW WHEN TOLERANCES ARE NOT MET ALSO PROVIDE COMPUTATIONS AND SWM REPORT REVISIONS.			
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	21.75 (MAX.)		
ESDv FLOW DEPTH (IN.)	3.0 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.25 FPS		
10-YR WATER SURFACE ELEVATION (FT)	22.31 (MAX)		
10-YR FLOW DEPTH (IN.)	11.8 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.57 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: $\square$ MDE $\square$ PRD
ACCEPTED BY:(NAME)	DATE:
REVISED 04-10-2018	

### STORMWATER MANAGEMENT NOTES:

- 1. CONSTRUCTION OF THE PROPOSED SHA BIORETENTION FACILITY WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 316 FOR 'STORMWATER MANAGEMENT (SWM) FILTRATION FACILITIES'.
- 2. ASBUILT CERTIFICATION WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 317 STORMWATER MANAGEMENT (SWM) FACILITY AS-BUILT CERTIFICATION.
- 3. UPON COMPLETION OF THE PROJECT, THE AS-BUILT CERTIFICATION MUST BE SIGNED; AND THE AS-BUILT PLANS (ALONG WITH THE FINAL STORMWATER MANAGÉMENT REPORT) MUST BE ELECTRONICALLY FORWARDED TO MS. KIONA LEAH (KLEAH@MDOT.MARYLAND.GOV). THIS WILL BE A CONDITION OF THE FINAL BOND.

NOTE: ANNE ARUNDEL COUNTY TO OWN, OPERATE AND MAINTAIN ESD 3-1, ESD 4-1, ESD 3-2, AND ESD 5-1


GP# G02018957

DWG. NO.:

REVISED 04-10-2018

PROFESSIONAL CERTIFICATION " I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY 4 NORTH PARK DRIVE ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 THE LAWS OF THE STATE OF MARYLAND." FAX: 410-785-6818

MD LICENSE NUMBER: 53587



REVISIONS ANNE ARUNDEL COUNTY	
NO. DESCRIPTION BY DATE DEPARTMENT OF PUBLIC WORKS	
APPROVED DATE APPROVED DATE SCALE: AS NOTED BROADNECK PENINSU	JLA TRAIL
Docusioned by: 11/20/2023   08:59 EST full dury 11/17/2023   08:0 DRAWN BY: DMT PHASE IB & V	
CHIEF ENGINEER PROJECT MANAGER CHECKED BY: DMT	
APPROVED DATE APPROVED DATE SHEET NO. 62_OF 116 STORMWATER MAN	IAGEMEN
Docustigned by:  Dovid C. Braun  11/17/2023   11:56 EST   Docustigned by:  Dovid C. Braun  11/17/2023   18:36 PROJECT NO. P504100  AS-BUILT	
ASSISTANT CHIEF ENGINEER CHIEF, RIGHT OF WAY CONTRACT NO. P504105	

# GRASS SWALE ESD-6-1 SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

WM FACILITY NUMBER	MDE/PRD NUMBER	SHA CONTRACT NUMBER
TBA	N/A	TRACKING NO. 20APAA014XX

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

			ı
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	6'		
TOTAL LENGTH (FT)	440'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION BELOW WHEN TOLERANCES ARE NOT MET. ALSO PROVIDE COMPUTATIONS AND SWM REPORT REVISIONS.			
FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	21.57 (MAX.)		
ESDv FLOW DEPTH (IN.)	3.2 IN.		
1-YR FLOW VELOCITY (FT/S) - MUST BE NON- EROSIVE	0.21 FPS		
10-YR WATER SURFACE ELEVATION (FT)	21.93 (MAX)		
10-YR FLOW DEPTH (IN.)	7.5 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.34 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: $\square$ MDE $\square$ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

#### GRASS SWALE ESD-6-2 SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 GRASS SWALES

TBA

MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

SWM FACILITY NUMBER | MDE/PRD NUMBER | SHA CONTRACT NUMBER

TRACKING NO. 20APAA014XX

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF CHECK DAMS	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	□ INSPECTION REPORT □ PHOTOGRAPHS  RELEASE STRUCTURE: □ INLET □ WEIR □ CHECK DAM □ OUTFALL □ NOT APPLICABLE □ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS SOD OR SOIL STABILIZATION MATTING AND TURFGRASS SEED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	8'		
TOTAL LENGTH (FT)	640'		
MAXIMUM CHANNEL SLOPE (FT/FT) – MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
NUMBER OF CHECK DAMS	N/A		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

ONLY COMPLETE THE PORTION BELOW WHEN TOLERANCES ARE NOT MET. ALSO PROVIDE COMPUTATIONS AND SWM REPORT REVISIONS.							
FEATURE	DESIGN	AS-BUILT	DIFFERENCE				
ESDv WATER SURFACE ELEVATION (FT)	22.61 (MAX.)						
ESDv FLOW DEPTH (IN.)	3.7 IN.						
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.23 FPS						
10-YR WATER SURFACE ELEVATION (FT)	23.06 (MAX)						
10-YR FLOW DEPTH (IN.)	9.1 IN.						
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.39 FPS						
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.						

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: ☐ MDE ☐ PRD
ACCEPTED BY:	DATE:
REVISED 04-10-2018	

NOTE: ANNE ARUNDEL COUNTY TO OWN, OPERATE AND MAINTAIN ESD 6-1, ESD 6-2, AND ESD 8-1

#### BIOSWALE ESD-8-1 SWM FACILITY AS-BUILT CERTIFICATION DATA TABLE FOR M-8 BIO-SWALES

SWM FACILITY NUMBER
TBA

MDE/PRD NUMBER
N/A

SHA CONTRACT NUMBER
TRACKING NO. 20APAA014XX

MAY ONLY BE CERTIFIED BY THE AS-BUILT ENGINEER (ABE) PER COMAR 26.17.02.10.

ACTIVITY	SUPPORTING DOCUMENTATION AND INFORMATION (SUBMIT WITH SWM FACILITY AS-BUILT CERTIFICATION PACKAGE)	DATE(S) OF INSPECTION
PRIOR TO SWM FACILITY EXCAVATION, OBSERVED ESC MEASURES ARE INSTALLED AROUND THE FACILITY OR CONFIRMED SURROUNDING AREA IS STABILIZED	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED EXCAVATION OF SWM FACILITY	□ INSPECTION REPORT □ PHOTOGRAPHS	
OBSERVED INSTALLATION OF GEOTEXTILE AND VERIFIED INSTALLATION PERFORMED AS SPECIFIED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF NO. 57 AGGREGATE BEDDING FOR SUB-DRAIN	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ NOT APPLICABLE	
OBSERVED INSTALLATION OF SUB- DRAIN, VERIFIED TYPE IS PPWP OR CPP-S, AND HAS SLOTTED	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ NOT APPLICABLE	
PERFORATIONS	PIPE TYPE: ☐ PPWP ☐ CPP-S	
OBSERVED INSTALLATION OF NO. 57 AGGREGATE AROUND AND ABOVE SUB-DRAIN	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ NOT APPLICABLE	
OBSERVED INSTALLATION OF NO. 7 AGGREGATE	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ NOT APPLICABLE	
OBSERVED INSTALLATION OF COARSE SAND	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ NOT APPLICABLE	
OBSERVED INSTALLATION OF APPROVED BIORETENTION SOIL MIX (BSM)	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ MATERIAL APPROVAL FORM	
OBSERVED INSTALLATION OF CHECK DAMS	□ INSPECTION REPORT □ PHOTOGRAPHS	
	☐ INSPECTION REPORT ☐ PHOTOGRAPHS	
OBSERVED INSTALLATION OF RELEASE STRUCTURE	RELEASE STRUCTURE: ☐ INLET ☐ WEIR ☐ CHECK DAM ☐ OUTFALL ☐ NOT APPLICABLE ☐ OTHER (WRITE IN):	
OBSERVED FINAL GRADING OF SWM FACILITY	□ INSPECTION REPORT □ PHOTOGRAPHS	
VERIFIED ESTABLISHMENT OF TURFGRASS AND OTHER VEGETATIVE SEED WITH SOIL STABILIZATION MATTING, INCLUDING PLUGS	☐ INSPECTION REPORT ☐ PHOTOGRAPHS ☐ LANDSCAPE ACCEPTANCE LETTER	

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
BOTTOM WIDTH (FT) – MAY NOT BE LESS THAN 2 FT OR EXCEED 8 FT	6'		
TOTAL LENGTH (FT)	530'		
MAXIMUM CHANNEL SLOPE (FT/FT) - MAY NOT EXCEED 4%	0.3%		
LEFT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
RIGHT SIDE SLOPE (H:V) – MAY NOT BE STEEPER THAN 3:1	3:1		
TOTAL THICKNESS OF NO. 57 AGGREGATE (IN.) – MAY NOT BE LESS THAN 18 IN.	18 <b>IN</b> .		
THICKNESS OF NO. 7 AGGREGATE (IN.) – MAY NOT BE LESS THAN 4 IN.	4 IN.		
THICKNESS OF COARSE SAND (IN.) – MAY NOT BE LESS THAN 4 IN.	4 IN.		
THICKNESS OF BSM (IN.) – MAY NOT BE LESS THAN 24 IN.	24 IN.		
SUB-DRAIN PIPE DIAMETER (IN.) – MAY NOT DIFFER FROM VALUE SPECIFIED	6 IN.		
SUB-DRAIN OUTLET INVERT ELEVATION (FT)	15.21		
NUMBER OF CHECK DAMS	8		
DISTANCE BETWEEN CHECK DAMS (FT)	SEE PROFILE		
CHECK DAM HEIGHT (FT)	SEE PROFILE		
TOP OF DITCH ELEVATION (FT)	SEE PROFILE		

FEATURE	DESIGN	AS-BUILT	DIFFERENCE
ESDv WATER SURFACE ELEVATION (FT)	21.97 (MAX.)		
ESDv FLOW DEPTH (IN.)	5.6 IN.		
1-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.37 FPS		
10-YR WATER SURFACE ELEVATION (FT)	22.48 (MAX)		
10-YR FLOW DEPTH (IN.)	11.8 IN.		
10-YR FLOW VELOCITY (FT/S) – MUST BE NON- EROSIVE	0.55 FPS		
10-YR FREEBOARD (IN.) – MAY NOT BE LESS THAN 9 IN. – MEASURED VERTICALLY FROM 10-YR WATER SURFACE ELEVATION TO PAVEMENT EDGE/SHOULDER	9 IN.		

SWM FACILITY AS-BUILT CERTIFICATION ACCEPTANCE	APPROVING AUTHORITY: $\square$ MDE $\square$ PRD
ACCEPTED BY:	DATE:
(NAME)	

REVISED 04-10-2018

#### STORMWATER MANAGEMENT AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT FACILITY (FACILITIES) SHOWN ON THE PLANS AND INDIVIDUALLY IDENTIFIED BELOW HAS (HAVE) BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS INCLUDED UNDER THE MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVAL, NUMBER \_\_\_\_\_\_ EXCEPT AS NOTED IN GREEN ON THE "ASBUILT" DRAWINGS. FURTHERMORE, THE GREEN-NOTED EXCEPTIONS DO NOT ADVERSELY AFFECT THE DESIGN AND/OR THE INTENDED PERFORMANCE OF THE FACILITY (FACILITIES)

ESD-8-1 (BIOSWALE)
INDIVIDUALLY BY A UNIQUE SWM FACILIT
•
Signature

"CERTIFY" MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED ON SUFFICIENT AND APPROPRIATE ONSITE INSPECTIONS AND MATERIAL TESTS

PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND,

NOTE: AS-BUILT CHECKLISTS CONTAINED IN THE CONTRACT DRAWINGS SHALL BE COMPLETED BY THE AS-BUILT INSPECTOR AND SUBMITTED TO THE SHA ALONG WITH THIS CERTIFICATION.

CONDUCTED DURING CONSTRUCTION.

FACILITY (FACILITIES).

Maryland Registration Number

NUMBER

#### STORMWATER MANAGEMENT AS-BUILT CERTIFICATION

I HEREBY CERTIFY THAT THE STORMWATER MANAGEMENT FACILITY (FACILITIES) SHOWN ON THE PLANS AND INDIVIDUALLY IDENTIFIED BELOW HAS (HAVE) BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS INCLUDED UNDER THE MARYLAND DEPARTMENT OF THE ENVIRONMENT APPROVAL, NUMBER \_\_\_\_\_\_ EXCEPT AS NOTED IN GREEN ON THE "ASBUILT" DRAWINGS. FURTHERMORE, THE GREEN-NOTED EXCEPTIONS DO NOT ADVERSELY AFFECT THE DESIGN AND/OR THE INTENDED PERFORMANCE OF THE

NRD-6-1 (NON-ROOFTOP DISCONNECT)
NRD-7-1 (NON-ROOFTOP DISCONNECT)
NRD-11-1 (NON-ROOFTOP DISCONNECT)
NRD-11-1 (NON-ROOFTOP DISCONNECT)
NRD-12-1 (NON-ROOFTOP DISCONNECT)
NRD-15-1 (NON-ROOFTOP DISCONNECT)
NRD-15-2 (NON-ROOFTOP DISCONNECT)
EACH SWM FACILITY IS IDENTIFIED INDIVIDUALLY BY A UNIQUE SWM FACILITY

Name (Printed)	Signature		

PROFESSIONAL CERTIFICATION. "I HEREBY CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND, LICENSE NO. , EXPIRATION DATE ."

"CERTIFY" MEANS TO STATE OR DECLARE A PROFESSIONAL OPINION BASED ON SUFFICIENT AND APPROPRIATE ONSITE INSPECTIONS AND MATERIAL TESTS CONDUCTED DURING CONSTRUCTION.

NOTE: AS-BUILT CHECKLISTS CONTAINED IN THE CONTRACT DRAWINGS SHALL BE COMPLETED BY THE AS-BUILT INSPECTOR AND SUBMITTED TO THE SHA ALONG WITH THIS CERTIFICATION.

#### STORMWATER MANAGEMENT NOTES:

- 1. CONSTRUCTION OF THE PROPOSED SHA BIORETENTION FACILITY WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 316 FOR 'STORMWATER MANAGEMENT (SWM) FILTRATION FACILITIES'.
- ASBUILT CERTIFICATION WILL CONFORM TO THE LATEST SHA STANDARD SPECIFICATION 317 STORMWATER MANAGEMENT (SWM) FACILITY AS-BUILT CERTIFICATION.
- 3. UPON COMPLETION OF THE PROJECT, THE AS-BUILT CERTIFICATION MUST BE SIGNED; AND THE AS-BUILT PLANS (ALONG WITH THE FINAL STORMWATER MANAGEMENT REPORT) MUST BE ELECTRONICALLY FORWARDED TO MS. KIONA LEAH (KLEAH@MDOT.MARYLAND.GOV). THIS WILL BE A CONDITION OF THE FINAL BOND.

GP# G02018957	DWG. NO.: SW-1
	300-1



AECOM 4 NORTH PARK DRIVE SUITE 300 HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818 PROFESSIONAL CERTIFICATION

"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND."

MD LICENSE NUMBER: 53587



REVISIONS						ANNE ARUNI	DEL COUNTY	•		
10.	DESCRIPTION	BY	DATE	DEPARTMENT OF PUBLIC WORKS						
				APPROVED	DATE	APPROVED	DATE	SCALE: AS NOT	ED	BROADNECK PENINSULA TRAIL
				DocuSigned by:	11/20/2023   08:5	9 EST Juli Autur	11/17/2023   08:0	ODRAWN BY:	DMT	PHASE IB & V
				CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT	
				APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>63</u> OF 116	STORMWATER MANAGEMENT
				DocuSigned by:  David C. Braun	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:	3 PROJECT NO.	P504100	AS-BUILT
				ASSISTANT CHIEF ENG	GINEER	CHIEF, RIGHT OF WAY		CONTRACT NO	. P504105	

#### **OUTFALL STATEMENTS:**

A FIELD INVESTIGATION OF THE MULTIPLE OUTFALLS WITHIN THE PROJECT AREA WAS PERFORMED IN FEBRUARY BY AECOM. BASED ON A HYDROLOGIC ANALYSIS WHICH INDICATED POST DEVELOPMENT PEAK DISCHARGE CHANGES 10% OR LESS FOR ALL OUTFALLS WITHIN THE PROJECT, THE OUTFALLS ARE DEEMED TO BE ADEQUATE PER ANNE ARUNDEL COUNTY STORMWATER MANAGEMENT MANUAL. THE PROJECT WILL NOT CONTRIBUTE TO THE ADVERSE IMPACTS AT THE OUTFALLS.

POINT OF INVESTIGATION # 1 (POI-1) IS LOCATED DOWNSTREAM OF AN EXISTING 22"X36" CMP CULVERT CROSSING COLLEGE PARKWAY AT STATION 7+80 THAT CONVEYS DRAINAGE FROM THE FOUR SEASONS AT SAINT MARGARETS DEVELOPMENT. THIS OFFSITE FROM AN ADJACENT DEVELOPMENT WILL HAVE NO ADVERSE IMPACT ON THE PROJECT AS THE DRAINAGE AREA WILL NOT CHANGE FROM THE EXISTING TO PROPOSED CONDITIONS. AN EXISTING 18" CMP ALSO DISCHARGES RUNOFF FROM EAST COLLEGE PARKWAY AT THIS LOCATION. THE OUTFALL IS STABLE AND CONSISTS OF A LARGE ROUGHLY TRAPEZOIDAL RIPRAP CHANNEL THAT DISCHARGES TO TWIN 30" RCP PIPES APPROXIMATELY 150' DOWNSTREAM. WITH THE PROPOSED IMPROVEMENTS, GRASS SWALE ESD 1-2 WILL UTILIZE THE EXISTING 18" CMP TO OUTFALL. A NEW 18" RCP WILL DISCHARGE GRASS SWALE ESD 1-1 ADJACENT TO THE EXISTING HEADWALL AT NON-EROSIVE VELOCITIES. THEREFORE, NO ADVERSE EFFECTS ARE ANTICIPATED AT THE EXISTING RIPRAP OUTFALL.

POINT OF INVESTIGATION # 2 (POI-2) IS LOCATED ADJACENT TO THE SULLIVAN PROPERTY AND CONVEYS A LARGE AMOUNT OF RUNOFF FROM THE NEARBY BUSINESSES, INCLUDING BAY HEAD INSURANCE AND DODGE & SONS PROPERTY. THE EXISTING OUTFALL IS STABLE AND CONSISTS OF A MARSH AREA WITH HEAVY VEGETATION. IN THE EXISTING CONDITIONS, FLOODING HAS BEEN REPORTED ALONG THE WEST EDGE OF SULLIVAN PROPERTY. THE PROPOSED CONDITIONS WILL IMPROVE THE OUTFALL ALONG THE SULLIVAN PROPERTY BY PLACING A STONE MATTING OUTFALL THAT WILL IMPROVE CAPACITY AND CREATE A MORE DEFINED CHANNEL DECREASING FLOOD EVENTS IN THIS AREA. IN ADDITION, A BIORETENTION FACILITY WILL BE PLACED UPSTREAM OF THE SULLIVAN PROPERTY WHICH WILL CAPTURE AND SLOW RUNOFF LEAVING THE SITE. THE PROPOSED PROJECT IMPROVEMENTS WILL HAVE NO ANTICIPATED ADVERSE IMPACTS AT POI-2.

LINE OF INVESTIGATION #3 (LOI-3) IS LOCATED FROM STATION 20+00, LT TO 22+20, LT. WHERE THE RUNOFF FROM THE PROJECT SHEET FLOWS IN A NORTHERLY DIRECTION TOWARDS A WOODED AREA ADJACENT TO THE REVELL DOWNS DEVELOPMENT. THE LINE OF INVESTIGATION IS WITHIN A STABLE WOODED AREA AND EVIDENCE OF EROSION, SEDIMENTATION OR FLOODING WAS NOT OBSERVED.

POINT OF INVESTIGATION #4 (POI-4) IS LOCATED JUST UPSTREAM OF THE EXISTING 24" CMP CULVERT CROSSING COLLEGE PARKWAY AT STATION 128+80. THE CULVERT CONVEYS DRAINAGE FROM EAST COLLEGE PARKWAY AND REVELL DOWNS DEVELOPMENT ULTIMATELY TO THE CLOSED DRAINAGE NETWORK ALONG US-50. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED CONDITIONS WILL CREATE A NEW OUTFALL AT EW-2/3 AND CONVEYS FLOWS FROM THE GRASS SWALE ESD 3-1 JUST UPSTREAM OF POI-4. RIRPAP WILL BE PLACED AT THE PROPOSED OUTFALL TO ENSURE NO ADVERSE IMPACTS DOWNSTREAM OF THE OUTFALL.

POINT OF INVESTIGATION #5 (POI-5) IS LOCATED JUST UPSTREAM OF THE EXISTING 24" CMP CULVERT CROSSING COLLEGE PARKWAY AT STATION 143+40. THE CROSSING CONVEYS DRAINAGE FROM EAST COLLEGE PARKWAY AND BAY HEAD ROAD ULTIMATELY TO THE CLOSED DRAINAGE NETWORK ALONG US-50. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE AT THE OUTFALL. THE EXISTING 18" RCP PIPE CROSSING AT BAY HEAD ROAD IS CLOGGED AND FULL OF SEDIMENT. THE PROPOSED CONDITIONS WILL REPLACE THE CLOGGED SYSTEM TO ENSURE POSITIVE DRAINAGE WITH THE GRADING IMPROVEMENTS. TWO (2) PIPE CROSSINGS UNDER THE TRAIL WILL MAINTAIN POSITIVE DRAINAGE TO THE OUTFALL AND DISCHARGE JUST UPSTREAM OF POI-5. RIRPAP WILL LINE THE CHANNEL NEAR THE OUTFALL TO ENSURE NO ADVERSE IMPACTS DOWNSTREAM OF THE OUTFALL.

POINT OF INVESTIGATION #6 (POI-6) IS LOCATED NEAR BAY HEAD PARK. DRAINAGE BETWEEN EAST COLLEGE PARKWAY AND BAY HEAD PARK IS MINIMAL AS IT IS FLAT AND HIGHLY WOODED. A PORTION OF BAY HEAD PARK AND SECTION OF THE WOODED AREA DRAINS TO A WETLAND AREA LOCATED SOUTH BAY HEAD PARK NEAR TRAIL STATION 608+75. THE OUTFALL IS STABLE AND NO EVIDENCE OF EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED TRAIL WILL MEET CRITERIA FOR NON-ROOFTOP DISCONNECT IN THE PARK AND MEET THE INTENT OF STORMWATER MANAGEMENT. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM DUE TO THE PROPOSED IMPROVEMENTS.

POINT OF INVESTIGATION #7 (POI-7) IS LOCATED JUST UPSTREAM OF THE EXISTING 24" RCP CULVERT CROSSING COLLEGE PARKWAY AT STATION 157+75. THE CROSSING CONVEYS DRAINAGE FROM EAST COLLEGE PARKWAY AND A FLAT WOODED AREA JUST SOUTH OF BAY HEAD PARK ULTIMATELY TO THE CLOSED DRAINAGE NETWORK ALONG US-50. THE OUTFALL IS STABLE AND NO EVIDENCE OF EROSION OR SEDIMENTATION IS VISIBLE. THE GRADES ARE VERY FLAT WITH SLOPES OF LESS THAN 0.3% IN SOME AREAS. SHALLOW PONDING OCCURS IN THE WOODED AREAS ADJACENT TO EAST COLLEGE PARKWAY, BUT NO EVIDENCE OF ROADWAY FLOODING. THE PROPOSED IMPROVEMENTS WILL ADEQUATLEY RAISE THE TRAIL IN THIS AREA TO ENSURE DRAINAGE ADJACENT AND UNDER THE TRAIL NEAR POI-7. THE PROPOSED GRASS SWALES AND DRAINAGE DITCHES WILL IMPROVE CONVEYANCE.

POINT OF INVESTIGATION #8 (POI-8) IS LOCATED JUST DOWNSTREAM OF THE EXISTING 24" RCP CULVERT CROSSING COLLEGE PARKWAY AT STATION 177+50. THE CROSSING CONVEYS DRAINAGE SOUTH OF EAST COLLEGE PARKWAY FROM SKIPMORE DRIVE UNDER US-50. THE OUTFALL IS STABLE AND NO EVIDENCE OF EROSION OR SEDIMENTATION IS VISIBLE. THE RUNOFF IS CONVEYED IN A ROUGHLY TRAPEZOIDAL NATURAL CHANNEL IN A NORTHERLY DIRECTION TO AN UNAMED TRIBUTARY OF MEREDITH CREEK. DUE TO THE LIMITED SPACE WITHIN THE RIGHT-OF-WAY AND PRESENCE OF STEEP SLOES THE PROPOSED TRAIL WILL BE CONSTRUCTED ALONG CURB AND GUTTER. THE PROPOSED CLOSED DRAINAGE SYSTEM WILL CONVEY RUNOFF FROM THE PROPOSED TRAIL AND EAST COLLEGE PARKWAYS AND DISCHARGE IT AT THE EXISTING OUTFALL PIPE AT POI-8.

POINT OF INVESTIGATION #9 (POI-9) IS LOCATED JUST USPTREAM OF THE EXISTING TWIN 24"X36, RCP CULVERT CROSSING COLLEGE PARKWAY AT TRAIL STATION 177+50. THE CROSSING CONVEYS MEREDITH CREEK UNDER US-50. THE OUTFALL IS A STABLE STREAM AND NO EVIDENCE OF EROSION OR SEDIMENTATION IS VISIBLE. THE PERENNIAL STREAM CONVEYS MOSTLY A LARGE DRAINAGE AREA OF UNDISTURBED WOODS AND SOME DEVELOPMENT OFF YORKTOWN ROAD. THE PROPOSED TRAIL WILL BE CONSTRUCTED ALONG CURB AND GUTTER DUE TO THE LIMITED SPACE WITHIN THE RIGHT-OF-WAY AND PRESENCE OF STEEP SLOPES. THE PROPOSED CLOSED DRAINAGE SYSTEM WILL CONVEY RUNOFF FROM THE PROPOSED TRAIL AND EAST COLLEGE PARKWAYS AND DISCHARGE IT JUST UPSTREAM OF THE EXISTING OUTFALL PIPE AT POI-9. THE OUTFALL IS DISCHARGING INTO A 100 YEAR FLOODPLAIN WHICH IS CONTAINED WITHIN ANNE ARUNDEL COUNTY RIGHT-OF-WAY.

POINT OF INVESTIGATION #10 (POI-10) IS LOCATED AT THE EXISTING INLET AT THE INTERSECTION OF EAST COLLEGE PARKWAY AND LOG INN ROAD. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED TRAIL WILL BE CONSTRUCTED ALONG CURB AND GUTTER DUE TO THE LIMITED SPACE WITHIN THE RIGHT-OF-WAY AND DISCHARGE TO THE EXISTING INLET MAINTAINING THE EXISTING DRAINAGE PATTERN. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM OF THE OUTFALL.

POINT OF INVESTIGATION #11 (POI-11) IS LOCATED JUST UPSTREAM OF THE EXISTING 60" RCP CULVERT CROSSING COLLEGE PARKWAY AT STATION 201+20. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE STREAM CONVEYS A LARGE DRAINAGE AREA OF UNDISTURBED WOODS AND A SMALL AMOUNT OF DEVELOPMENT OFF LOG INN ROAD ULTIMATELY TO THE CLOSED DRAINAGE NETWORK ALONG US-50. MOST OF THE PROPOSED TRAIL WITHIN THE STANDY POINT STATE PARK WILL ULTIMATELY OUTFALL AT THIS LOCATION. THE PROPOSED TRAIL WILL MEET CRITERIA FOR NON-ROOFTOP DISCONNECT THROUGHOUT THE PARK AND WILL MEET THE INTENT OF STORMWATER MANAGEMENT. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM OF THE OUTFALL.

LINE OF INVESTIGATION #12 (LOI-12) IS LOCATED NEAR SANDY POINT STATE PARK MAINTANANCE. IN THIS SECTION OF THE PARK, THERE ARE NO CLEAR DRAINAGE PATHS WITHIN THE FLAT SECTION OF WOODS. LOI-12 IS SHEET FLOW FROM THE PARK THAT LEAVES THE SITE FROM TRAIL STATION 339+00 TO STATION 345+80 IN A NORTHERLY DIRECTION. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED TRAIL WILL MEET CRITERIA FOR NON-ROOFTOP DISCONNECT IN THE PARK AND MEET THE INTENT OF STORMWATER MANAGEMENT. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM DUE TO THE PROPOSED IMPROVEMENTS.

POINT OF INVESTIGATION #13 (POI-13) IS LOCATED JUST DOWNSTREAM OF A NATURAL DITCH IN SANDY POINT STATE PARK THAT FLOWS IN A NORTHERLY DIRECTION TO A HIGHLY WOODED AREA. THE DRAINAGE BETWEEN OCEANIC DRIVE AND SOUTH BEACH ROAD FOR THIS PORTION AREA OF THE PROJECT ULTIMATELY OUTFALLS TO THIS LOCATION. THE OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED TRAIL WILL MEET CRITERIA FOR NON-ROOFTOP DISCONNECT IN THE PARK AND MEET THE INTENT OF STORMWATER MANAGEMENT. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM DUE TO THE PROPOSED IMPROVEMENTS.

POINT OF INVESTIGATION #14 (POI-14) IS LOCATED NEAR SANDY POINT STATE PARK KIOSK. THERE IS A SMALL PORTION OF PROPOSED WORK THAT DISCHARGES THE OPPOSITE DIRECTION OF THE OTHER POIL S AND LOIL S AFTER THE HIGH POINT NEAR TRAIL STATION 407+00. OUTFALL IS STABLE AND NO EVIDENCE OF FLOODING, EROSION OR SEDIMENTATION IS VISIBLE. THE PROPOSED TRAIL WILL MEET CRITERIA FOR NON-ROOFTOP DISCONNECT IN THE PARK AND MEET THE INTENT OF STORMWATER MANAGEMENT. NO ADVERSE IMPACTS ARE ANTICIPATED DOWNSTREAM DUE TO THE PROPOSED IMPROVEMENTS.

BASED ON THE SITE INVESTIGATION, EXISTING CONDITIONS, THE PROPOSED IMPROVEMENTS, AND THE PROPOSED STORMWATER MANAGEMENT PRACTICES, IT HAS BEEN CONCLUDED THAT THE PROJECT WILL HAVE NO ADVERSE IMPACT ON THE ULTIMATE DOWNSTREAM RECEIVING WATERWAY.

#### STORMWATER MANAGEMENT NOTES:

- 1. STORMWATER MANAGEMENT FOR THIS PROJECT SHALL BE APPROVED IN ACCORDANCE WITH ARTICLE 16 AND 17 OF THE ANNE ARUNDEL COUNTY ORDINANCE; AND ENVIRONMENT ARTICLE, TITLE 4, SUBTITLE 2, OF THE ANNOTATED CODE OF MARYLAND, AND THE APPROVED STORMWATER MANAGEMENT PLANS ARE ON FILE WITH THE OFFICE OF PLANNING AND ZONING.
- 2. METHODS FOR STORMWATER MANAGEMENT INCLUDE THE USE OF NON-ROOFTOP DISCONNECT. GRASS SWALES. BIOSWALES AND BIORETENTION.
- 3. THIS PROJECT WILL ADD (NET) ABOUT 3.5 ACRES OF IMPERVIOUS AREA SPREAD OUT OVER NUMEROUS POINTS OF INVESTIGATION (POI) AND LINE OF INVESTIGATION (LOI) DISTRIBUTED OVER THE LENGTH OF THIS LINEAR PROJECT. SEE STORMWATER MANAGEMENT REPORT FOR DETAILED INFORMATION.

#### **Table B.3.2 Materials Specifications for Bioretention**

Material	Specification	Size	Notes
Plantings	see Appendix A, Table A.4	n/a	plantings are site-specific
planting soil [2.5' to 4' deep]	sand 35 - 60% silt 30 - 55% clay 10 - 25%	n/a	USDA soil types loamy sand, sandy loam or loam
mulch	shredded hardwood		aged 6 months, minimum
pea gravel diaphragm and curtain drain	pea gravel: ASTM-D-448 ornamental stone: washed cobbles	pea gravel: No. 6 stone: 2" to 5"	
geotextile	Class "C" - apparent opening size (ASTM-D-4751), grab tensile strength (ASTM-D-4632), puncture resistance (ASTM-D-4833)	n/a	for use as necessary beneath underdrains only
underdrain gravel	AASHTO M-43	0.375" to 0.75"	
underdrain piping	F 758, Type PS 28 or AASHTO M-278	4" to 6" rigid schedule 40 PVC or SDR35	3/8" perf. @ 6" on center, 4 holes per row; minimum of 3" of gravel over pipes; not necessary underneath pipes
poured in place concrete (if required)	MSHA Mix No. 3; f'c = 3500 psi @ 28 days, normal weight, air-entrained; reinforcing to meet ASTM-615-60	n/a	on-site testing of poured-in-place concrete required: 28 day strength and slump test; all concrete design (cast-in-place or pre-cast) <i>not using previously approved State or local standards</i> requires design drawings sealed and approved by a professional structural engineer licensed in the State of Maryland - design to include meeting ACI Code 350.R/89; vertical loading [H-10 or H-20]; allowable horizontal loading (based on soil pressures); and analysis of potential cracking
sand [1' deep]	AASHTO-M-6 or ASTM-C-33	0.02" to 0.04"	Sand substitutions such as Diabase and Graystone #10 are not acceptable. No calcium carbonated or dolomitic sand substitutions are acceptable. No "rock dust" can be used for sand.

### **B.3.B SPECIFICATIONS FOR BIORETENTION**

1. MATERIAL SPECIFICATIONS

THE ALLOWABLE MATERIALS TO BE USED IN BIORETENTION AREA ARE DETAILED IN TABLE B.3.2.

2. PLANTING S

THE SOIL SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES. NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE BIORETENTION AREA THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS. THE PLANTING SOIL SHALL BE FREE OF BERMUDA GRASS, QUACKGRASS, JOHNSON GRASS, OR OTHERNOXIOUS WEEDS AS SPECIFIED UNDER COMAR 15.08.01.05.

THE PLANTING SOIL SHALL BE TESTED AND SHALL MEET THE FOLLOWING CRITERIA:

-PH RANGE 5.2 - 7.0 -ORGANIC MATTER 1.5 - 4% (BY WEIGHT) -MAGNESIUM 35 LB./AC -PHOSPHORUS (PHOSPHATE - P2O5) 75 LB./AC -POTASSIUM (POTASH - K2O) 85 LB./AC

-SOLUBLE SALTS NOT TO EXCEED 500 PPM

ALL BIORETENTION AREAS SHALL HAVE A MINIMUM OF ONE TEST. EACH TEST SHALL CONSIST OF BOTH THE STANDARD SOIL TEST FOR PH, PHOSPHORUS, AND POTASSIUM AND ADDITIONAL TESTS OF ORGANIC MATTER, AND SOLUBLE SALTS. A TEXTURAL ANALYSIS IS REQUIRED FROM THE SITE STOCKPILED TOPSOIL. IF TOPSOIL IS IMPORTED, THEN A TEXTURE ANALYSIS SHALL BE PERFORMED FOR EACH LOCATION WHERE THE TOP SOIL WAS EXCAVATED.

SINCE DIFFERENT LABS CALIBRATE THEIR TESTING EQUIPMENT DIFFERENTLY, ALL TESTING RESULTS SHALL COME FROM THE SAME TESTING FACILITY.

SHOULD THE PH FALL OUT OF THE ACCEPTABLE RANGE, IT MAY BE MODIFIED (HIGHER) WITH LIME OR (LOWER) WITH IRON SULFATE PLUS SULFUR.

. COMPACTION

IT IS VERY IMPORTANT TO MINIMIZE COMPACTION OF BOTH THE BASE OF THE BIORETENTION AREA AND THE REQUIRED BACKFILL. WHEN POSSIBLE, USE EXCAVATION HOES TO REMOVE ORIGINAL SOIL. IF BIORETENTION AREAS ARE EXCAVATED USING A LOADER, THE CONTRACTOR SHOULD USE WIDE TRACK OR MARSH TRACK EQUIPMENT, OR LIGHT EQUIPMENT WITH TURF TYPE TIRES. USE OF EQUIPMENT WITH NARROW TRACKS OR NARROW TIRES, RUBBER TIRES WITH LARGE LUGS, OR HIGH PRESSURE TIRES WILL CAUSE EXCESSIVE COMPACTION RESULTING IN REDUCED INFILTRATION RATES AND IS NOT ACCEPTABLE. COMPACTION WILL SIGNIFICANTLY CONTRIBUTE TO DESIGN FAILURE.

COMPACTION CAN BE ALLEVIATED AT THE BASE OF THE BIORETENTION FACILITY BY USING A PRIMARY TILLING OPERATION SUCH AS A CHISEL PLOW, RIPPER, OR SUBSOILER. THESE TILLING OPERATIONS ARE TO REFRACTURE THE SOIL PROFILE THROUGH THE 12 INCH COMPACTION ZONE. SUBSTITUTE METHODS MUST BE APPROVED BY THE ENGINEER. ROTOTILLERS TYPICALLY DO NOT TILL DEEP ENOUGH TO REDUCE THE EFFECTS OF COMPACTION FROM HEAVY EQUIPMENT.

ROTOTILL 2 TO 3 INCHES OF SAND INTO THE BASE OF THE BIORETENTION FACILITY BEFORE BACKFILLING THE OPTIONAL SAND LAYER. PUMP ANY PONDED WATER BEFORE PREPARING (ROTOTILLING) BASE.

WHEN BACKFILLING THE TOPSOIL OVER THE SAND LAYER, FIRST PLACE 3 TO 4 INCHES OF TOPSOIL OVER THE SAND, THEN ROTOTILL THE SAND/TOPSOIL TO CREATE A GRADATION ZONE. BACKFILL THE REMAINDER OF THE TOPSOIL TO FINAL GRADE.

WHEN BACKFILLING THE BIORETENTION FACILITY, PLACE SOIL IN LIFTS 12"TO 18". DO NOT USE HEAVY EQUIPMENT WITHIN THE BIORETENTION BASIN. HEAVY EQUIPMENT CAN BE USED AROUND THE PERIMETER OF THE BASIN TO SUPPLY SOILS AND SAND. GRADE BIORETENTION MATERIALS WITH LIGHT EQUIPMENT SUCH AS A COMPACT LOADER OR A DOZER/LOADER WITH MARSH TRACKS.

4. PLANT MATERIAL

THE PLANT MATERIALS TO BE USED ON THE PROJECT ARE SHOWN ON THE LANDSCAPE PLANS ACCRODING TO THE LIST OF RECOMMENDED PLANT MATERIAL FOR BIORETENTION AREAS (APPENDIX A, SECTION A.2.3)

5. PLANT INSTALLATION

MULCH SHOULD BE PLACED TO A UNIFORM THICKNESS OF 2"TO 3". SHREDDED HARDWOOD MULCH IS THE ONLY ACCEPTED MULCH. PINE MULCH AND WOOD CHIPS WILL FLOAT AND MOVE TO THE PERIMETER OF THE BIORETENTION AREA DURING A STORM EVENT AND ARE NOT ACCEPTABLE. SHREDDED MULCH MUST BE WELL AGED

(6 TO 12 MONTHS) FOR ACCEPTANCE.

ROOT STOCK OF THE PLANT MATERIAL SHALL BE KEPT MOIST DURING TRANSPORT AND ON-SITE STORAGE. THE PLANT ROOT BALL SHOULD BE PLANTED SO 1/8TH OF THE BALL IS ABOVE FINAL GRADE SURFACE. THE DIAMETER OF THE PLANTING PIT SHALL BE AT LEAST SIX INCHES LARGER THAN THE DIAMETER OF THE PLANTING BALL. SET AND MAINTAIN THE PLANT STRAIGHT DURING THE ENTIRE PLANTING PROCESS. THOROUGHLY WATER GROUND BED COVER AFTER INSTALLATION. TREES SHALL BE BRACED USING 2"BY 2" STAKES ONLY AS NECESSARY AND FOR THE FIRST GROWING SEASON ONLY. STAKES ARE TO BE EQUALLY SPACED ON THE OUTSIDE OF THE TREE BALL.

GRASSES AND LEGUME SEED SHOULD BE DRILLED INTO THE SOIL TO A DEPTH OF AT LEAST ONE INCH. GRASS AND LEGUME PLUGS SHALL BE PLANTED FOLLOWING THE NON-GRASS GROUND COVER PLANTING SPECIFICATIONS.

THE TOPSOIL SPECIFICATIONS PROVIDE ENOUGH ORGANIC MATERIAL TO ADEQUATELY SUPPLY NUTRIENTS FROM NATURAL CYCLING. THE PRIMARY FUNCTION OF THE BIORETENTION STRUCTURE IS TO IMPROVE WATER QUALITY. ADDING FERTILIZERS DEFEATS, OR AT A MINIMUM, IMPEDES THIS GOAL. ONLY ADD FERTILIZER IF WOOD CHIPS OR MULCH ARE USED TO AMEND THE SOIL. ROTOTILL UREA FERTILIZER AT A RATE OF 2 POUNDS PER 1000 SQUARE FEET.

6. UNDERDRAINS

UNDERDRAINS ARE TO BE PLACED ON A 3'-0" WIDE SECTION OF FILTER CLOTH. PIPE IS PLACED NEXT, FOLLOWED BY THE GRAVEL BEDDING. THE ENDS OF UNDERDRAIN PIPES NOT TERMINATING IN AN OBSERVATION WELL SHALL BE CAPPED. THE MAIN COLLECTOR PIPE FOR UNDERDRAIN SYSTEMS SHALL BE CONSTRUCTED AT A MINIMUM SLOPE OF 0.5%. OBSERVATION WELLS AND/OR CLEAN-OUT PIPES MUST BE PROVIDED (ONE MINIMUM PER EVERY 1000 SQUARE FEET OF SURFACE AREA).

DWG. NO.:

SWD-01

GP# G02018957

7. MISCELLANEOUS

THE BIORETENTION FACILITY MAY NOT BE CONSTRUCTED UNTIL ALL CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED.

**AECOM** 

AECOM 4 NORTH PARK DRIVE SUITE 300 HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818 PROFESSIONAL CERTIFICATION

"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND."

MD LICENSE NUMBER: 53587



											OVVD 01	
REVISIONS					ANNE ARUNDEL COUNTY							
63	NO. DESCRIPTION BY DATE				DEPARTMENT OF PUBLIC WORKS							
					APPROVED	DATE	APPROVED	DATE	SCALE: AS NOT	ED	BROADNECK PENINSULA TRAIL	
=					Docusigned by:	11/20/2023   08:5	9 EST Juli Autur	11/17/2023   08:0	1D <b>RA</b> WN BY:	DMT	PHASE IB & V	
					CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT		
					APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>64</u> OF 116	STORMWATER MANAGEMEN <sup>*</sup>	
					DocuSigned by:  **David C. Braun**	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:3	PROJECT NO.	P504100	NOTES AND DETAILS	
23					ASSISTANT CHIEF EN	GINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	P504105		

#### B.4.C SPECIFICATIONS FOR BIOSWALES

#### 1. MATERIAL SPECIFICATIONS

THE ALLOWABLE MATERIALS TO BE USED IN THESE PRACTICES ARE DETAILED IN TABLE B.4.1.

#### 2. FILTERING MEDIA OR PLANTING SOIL

THE SOIL SHALL BE A UNIFORM MIX, FREE OF STONES, STUMPS, ROOTS OR OTHER SIMILAR OBJECTS LARGER THAN TWO INCHES, NO OTHER MATERIALS OR SUBSTANCES SHALL BE MIXED OR DUMPED WITHIN THE MICROBIORETENTION PRACTICE THAT MAY BE HARMFUL TO PLANT GROWTH, OR PROVE A HINDRANCE TO THE PLANTING OR MAINTENANCE OPERATIONS. THE PLANTING SOIL SHALL BE FREE OF BERMUDA GRASS, QUACKGRASS, JOHNSON GRASS, OR OTHER NOXIOUS WEEDS AS SPECIFIED UNDER COMAR 15.08.01.05.

#### THE PLANTING SOIL SHALL BE TESTED AND SHALL MEET THE FOLLOWING CRITERIA:

- SOIL COMPONENT LOAMY SAND OR SANDY LOAM (USDA SOIL TEXTURAL CLASSIFICATION)
- ORGANIC CONTENT MINIMUM 10% BY DRY WEIGHT (ASTM D 2974) . IN GENERAL, THIS CAN BE MET WITH A MIXTURE OF LOAMY SAND (60%-65%) AND COMPOST (35% TO 40%) OR SANDY LOAM (30%) COARSE SAND (30%), AND COMPOST (40%)
- CLAY CONTENT MEDIA SHALL HAVE A CLAY CONTENT OF LESS THAN 5%.
- PH RANGE SHOULD BE BETWEEN 5.5 7.0. AMENDMENTS (E.G., LIME, IRON SULFATE PLUS SULFUR) MAY BE MIXED INTO THE SOIL TO INCREASE OR DECREASE PH.

THERE SHALL BE AT LEAST ONE SOIL TEST PER PROJECT. EACH TEST SHALL CONSIST OF BOTH THE STANDARD SOIL TEST FOR PH. AND ADDITIONAL TESTS OF ORGANIC MATTER. AND SOLUBLE SALTS. A TEXTURAL ANALYSIS IS REQUIRED FROM THE SITE STOCKPILED TOPSOIL, IF TOPSOIL IS IMPORTED, THEN A TEXTURE ANALYSIS SHALL BE PERFORMED FOR EACH LOCATION WHERE THE TOPSOIL WAS EXCAVATED.

#### 3. COMPACTION

IT IS VERY IMPORTANT TO MINIMIZE COMPACTION OF BOTH THE BASE OF BIORETENTION PRACTICES AND THE REQUIRED BACKFILL. WHEN POSSIBLE, USE EXCAVATION HOES TO REMOVE ORIGINAL SOIL. IF PRACTICES ARE EXCAVATED USING A LOADER, THE CONTRACTOR SHOULD USE WIDE TRACK OR MARSH TRACK EQUIPMENT. OR LIGHT EQUIPMENT WITH TURF TYPE TIRES. USE OF EQUIPMENT WITH NARROW TRACKS OR NARROW TIRES, RUBBER TIRES WITH LARGE LUGS, OR HIGH-PRESSURE TIRES WILL CAUSE EXCESSIVE COMPACTION RESULTING IN REDUCED

INFILTRATION RATES AND IS NOT ACCEPTABLE. COMPACTION WILL SIGNIFICANTLY CONTRIBUTE TO DESIGN FAILURE.

COMPACTION CAN BE ALLEVIATED AT THE BASE OF THE BIORETENTION FACILITY BY USING A PRIMARY TILLING OPERATION SUCH AS A CHISEL PLOW, RIPPER, OR SUBSOILER. THESE TILLING OPERATIONS ARE TO REFRACTURE THE SOIL PROFILE THROUGH THE 12 INCH COMPACTION ZONE. SUBSTITUTE METHODS MUST BE APPROVED BY THE ENGINEER. ROTOTILLERS TYPICALLY DO NOT TILL DEEP ENOUGH TO REDUCE THE EFFECTS OF COMPACTION FROM HEAVY EQUIPMENT.

ROTOTILL 2 TO 3 INCHES OF SAND INTO THE BASE OF THE BIORETENTION FACILITY BEFORE BACKFILLING THE OPTIONAL SAND LAYER. PUMP ANY PONDED WATER BEFORE PREPARING (ROTOTILLING) BASE.

WHEN BACKFILLING THE TOPSOIL OVER THE SAND LAYER. FIRST PLACE 3 TO 4 INCHES OF TOPSOIL OVER THE SAND, THEN ROTOTILL THE SAND/TOPSOIL TO CREATE A GRADATION ZONE. BACKFILL THE REMAINDER OF THE TOPSOIL TO FINAL GRADE.

WHEN BACKFILLING THE BIORETENTION FACILITY, PLACE SOIL IN LIFTS 12"TO 18". DO NOT USE HEAVY EQUIPMENT WITHIN THE BIORETENTION BASIN. HEAVY EQUIPMENT CAN BE USED AROUND THE PERIMETER OF THE BASIN TO SUPPLY SOILS AND SAND. GRADE BIORETENTION MATERIALS WITH LIGHT EQUIPMENT SUCH AS A COMPACT LOADER OR A DOZER/LOADER WITH MARSH TRACKS.

RECOMMENDED PLANT MATERIAL FOR BIOSWALE PRACTICES ARE SHOWN ON THE LANDSCAPE PLANS.

COMPOST IS A BETTER ORGANIC MATERIAL SOURCE, IS LESS LIKELY TO FLOAT, AND SHOULD BE PLACED IN THE INVERT AND OTHER LOW AREAS. MULCH SHOULD BE PLACED IN SURROUNDING TO A UNIFORM THICKNESS OF 2" TO 3". SHREDDED OR CHIPPED HARDWOOD MULCH IS THE ONLY ACCEPTED MULCH, PINE MULCH AND WOOD CHIPS WILL FLOAT AND MOVE TO THE PERIMETER OF THE BIORETENTION AREA DURING A STORM EVENT AND ARE NOT ACCEPTABLE. SHREDDED MULCH MUST BE WELL AGED (6 TO 12 MONTHS) FOR ACCEPTANCE.

ROOTSTOCK OF THE PLANT MATERIAL SHALL BE KEPT MOIST DURING TRANSPORT AND ON-SITE STORAGE THE PLANT ROOT BALL SHOULD BE PLANTED SO 1/8TH OF THE BALL IS ABOVE FINAL GRADE SURFACE. THE DIAMETER OF THE PLANTING PIT SHALL BE AT LEAST SIX INCHES LARGER THAN THE DIAMETER OF THE PLANTING BALL. SET AND MAINTAIN THE PLANT STRAIGHT DURING THE ENTIRE PLANTING PROCESS. THOROUGHLY WATER GROUND BED COVER AFTER INSTALLATION.

TREES SHALL BE BRACED USING 2" BY 2" STAKES ONLY AS NECESSARY AND FOR THE FIRST GROWING SEASON ONLY. STAKES ARE TO BE EQUALLY SPACED ON THE OUTSIDE OF THE TREE BALL.

GRASSES AND LEGUME SEED SHOULD BE DRILLED INTO THE SOIL TO A DEPTH OF AT LEAST ONE INCH. GRASS AND LEGUME PLUGS SHALL BE PLANTED FOLLOWING THE NON-GRASS GROUND COVER PLANTING SPECIFICATIONS.

THE TOPSOIL SPECIFICATIONS PROVIDE ENOUGH ORGANIC MATERIAL TO ADEQUATELY SUPPLY NUTRIENTS FROM NATURAL CYCLING. THE PRIMARY FUNCTION OF THE BIORETENTION STRUCTURE IS TO IMPROVE WATER QUALITY. ADDING FERTILIZERS DEFEATS, OR AT A MINIMUM, IMPEDES THIS GOAL. ONLY ADD FERTILIZER IF WOOD CHIPS OR MULCH ARE USED TO AMEND THE SOIL. ROTOTILL UREA FERTILIZER AT A RATE OF 2 POUNDS PER 1000 SQUARE FEET.

#### 6. UNDERDRAINS

#### UNDERDRAINS SHOULD MEET THE FOLLOWING CRITERIA:

- PIPE- SHOULD BE 4" TO 6" DIAMETER, SLOTTED OR PERFORATED RIGID PLASTIC PIPE (ASTMF 758, TYPE PS 28, OR AASHTO-M-278) IN A GRAVEL LAYER. THE PREFERRED MATERIAL IS SLOTTED, 4" RIGID PIPE
- PERFORATIONS IF PERFORATED PIPE IS USED, PERFORATIONS SHOULD BE %" DIAMETER LOCATED 6" ON CENTER WITH A MINIMUM OF FOUR HOLES PER ROW. PIPE SHALL BE WRAPPED WITH A 1/4" (NO. 4 OR 4X4) GALVANIZED HARDWARE CLOTH.
- GRAVEL- THE GRAVEL LAYER (NO. 57 STONE PREFERRED) SHALL BE AT LEAST 3" THICK ABOVE AND
- BELOW THE UNDERDRAIN. • THE MAIN COLLECTOR PIPE SHALL BE AT A MINIMUM 0.3% SLOPE.
- A RIGID, NON-PERFORATED OBSERVATION WELL MUST BE PROVIDED (ONE PER EVERY 1,0000 SQUARE
- FEET) TO PROVIDE A CLEAN-OUT PORT AND MONITOR PERFORMANCE OF THE FILTER. • A 4"LAYER OF PEA GRAVEL (1/8"TO 3/8"STONE) SHALL BE LOCATED BETWEEN THE FILTER MEDIA AND UNDERDRAIN TO PREVENT MIGRATION OF FINES INTO THE UNDERDRAIN. THIS LAYER MAY BE CONSIDERED PART OF THE FILTER

BED WHEN BED THICKNESS EXCEEDS 24". THE MAIN COLLECTOR PIPE FOR UNDERDRAIN SYSTEMS SHALL BE CONSTRUCTED AT A MINIMUM SLOPE OF 0.3%. OBSERVATION WELLS AND/OR CLEAN-OUT PIPES MUST BE PROVIDED (ONE MINIMUM PER EVERY 1000 SQUARE FEET OF SURFACE AREA) .

#### 7. MISCELLANEOUS

THESE PRACTICES MAY NOT BE CONSTRUCTED UNTIL ALL CONTRIBUTING DRAINAGE AREA HAS BEEN STABILIZED

Table B.4.1 Materials Sp	pecifications for Micro-Bioreto	ention, Rain Gardens &	Landscape Infiltration-
Material	Specification	Size	Notes
Plantings	see Appendix A, Table A.4	n/a	plantings are site-specific
Planting soil [2' to 4' deep]	loamy sand (60 - 65%) & compost (35 - 40%) or sandy loam (30%), coarse sand (30%) & compost (40%)	n/a	USDA soil types loamy sand or sandy loam; clay content < 5%
Organic content	Min. 10% by dry weight (ASTM D 2974)		
Mulch	shredded hardwood		aged 6 months, minimum; no pine or wood chips
Pea gravel diaphragm	pea gravel: ASTM-D-448	NO. 8 OR NO. 9 (1/8" TO 3/8")	
Curtain drain	ornamental stone: washed cobbles	stone: 2" to 5"	
Geotextile		n/a	PE Type 1 nonwoven
Gravel (underdrains and infiltration berms)	AASHTO M-43	NO. 57 OR NO. 6 AGGREGATE (3/8" to 3/4")	
Underdrain piping	F 758, Type PS 28 or AASHTO M-278	4" to 6" rigid schedule 40 PVC or SDR35	Slotted or perforated pipe; 3/8" perf. @ 6" on center, 4 holes per row; minimum of 3" of gravel over pipes; not necessary underneath pipes. Perforated pipe shall be wrapped with ¼-inch galvanized hardware cloth
Poured in place concrete (if required)	MSHA Mix No. 3; f° <sub>c</sub> = 3500 psi @ 28 days, normal weight, air-entrained; reinforcing to meet ASTM-615-60	n/a	on-site testing of poured-in-place concrete required: 28 day strength and slump test; all concrete design (cast-in-place or pre-cast) <i>not using previously approved State or local standards</i> requires design drawings sealed and approved by a professional structural engineer licensed in the State of Maryland - design to include meeting ACI Code 350.R/89; vertical loading [H-10 or H-20]; allowable horizontal loading (based on soil pressures); and analysis of potential cracking
Sand	AASHTO-M-6 or ASTM-C-33	0.02" to 0.04"	Sand substitutions such as Diabase and Graystone ( <b>AASHTO</b> ) #10 are not acceptable. No calcium carbonated or dolomitic sand substitutions are acceptable. No "rock dust" can be used for sand.

#### STORMWATER MANAGEMENT GENERAL NOTES:

- COORDINATES ARE BASED ON THE MARYLAND STATE COORDINATE SYSTEM NAD 83 DATUM PROJECTED BY THE DEPARTMENT OF PUBLIC WORKS OF ANNE ARUNDEL COUNTY, MARYLAND.
- ELEVATIONS ARE BASED ON THE U.S.C. AND G.S. 1929 DATUM PROJECTED BY THE ANNE ARUNDEL COUNTY OFFICE OF PLANNING AND ZONING.
- ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH THE MOST CURRENT VERSION OF THE ANNE ARUNDEL COUNTY DEPARTMENT OF PUBLIC WORKS STANDARD DETAILS FOR CONSTRUCTION OF STORM DRAINS, ROADS AND STORMWATER MANAGEMENT.
- 4. NECESSARY PRECAUTIONS SHALL BE TAKEN BY THE CONTRACTOR TO PROTECT EXISTING SERVICES AND MAINS. ANYDAMAGE TO EXISTING SERVICES AND MAINS DUE TO THEIR NEGLIGENCE SHALL BE REPAIRED IMMEDIATELY AT THE CONTRACTOR'S EXPENSE.
- 5. THE EXISTING UTILITIES AND OBSTRUCTIONS SHOWN ARE FROM THE BEST AVAILABLE RECORDS AND SHALL BE VERIFIED BY THE CONTRACTOR TO HIS OWN SATISFACTION BEFORE STARTING CONSTRUCTION. NEITHER THE OWNER NOR ANNE ARUNDEL COUNTY DEPARTMENT OF PUBLIC WORKS WARRANT OR GUARANTEE THE COMPLETENESS OR THE CORRECTNESS OF THE INFORMATION GIVEN.
- IT SHALL BE DISTINCTLY UNDERSTOOD THAT FAILURE TO SPECIFICALLY MENTION ANY WORK WHICH WOULD NORMALLY BE REQUIRED TO COMPLETE THE PROJECT SHALL NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY TO PERFORM SUCH WORK.
- 7. THE CONTRACTOR SHALL NOTIFY ALL UTILITY COMPANIES AT LEAST 5 DAYS PRIOR TO STARTING CONSTRUCTION OF THIS PROJECT.
- 8. THE CONTRACTOR SHALL NOTIFY THE ANNE ARUNDEL COUNTY DEPARTMENT OF INSPECTION AND PERMITS FIVE (5) WORKING DAYS BEFORE STARTING WORK SHOWN ON THE DRAWINGS.
- THE CONTRACTOR SHALL NOTIFY MISS UTILITY@ 1-800-257-7777 FIVE (5) WORKING DAYS BEFORE STARTING WORK SHOWN ON THESE DRAWINGS.
- 10. ALL UTILITY POLES SHALL BE BRACED AS NECESSARY AT CONTRACTOR'S EXPENSE. UTILITY POLES SHALL BE RELOCATED AT THE OWNER'S EXPENSE IN CASES WHERE THEY WILL INTERFERE WITH CONSTRUCTION.
- 11. PIPE ELEVATIONS REFER TO INVERTS UNLESS OTHERWISE NOTED.

PROFESSIONAL CERTIFICATION

THE LAWS OF THE STATE OF

MD LICENSE NUMBER: 53587

EXPIRATION DATE: 12-09-2024

MARYLAND."

" I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY

ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER

	Specification	Size	Notes
	see Appendix A, Table A.4	n/a	plantings are site-specific
	loamy sand (60 - 65%) & compost (35 - 40%) or sandy loam (30%), coarse sand (30%) & compost (40%)	n/a	USDA soil types loamy sand or sandy loam; clay content < 5%
	Min. 10% by dry weight (ASTM D 2974)		
	shredded hardwood		aged 6 months, minimum; no pine or wood chips
ıgm	pea gravel: ASTM-D-448	NO. 8 OR NO. 9 (1/8" TO 3/8")	
	ornamental stone: washed cobbles	stone: 2" to 5"	
		n/a	PE Type 1 nonwoven
ns and	AASHTO M-43	NO. 57 OR NO. 6 AGGREGATE (3/8" to 3/4")	
5	F 758, Type PS 28 or AASHTO M-278	4" to 6" rigid schedule 40 PVC or SDR35	Slotted or perforated pipe; 3/8" perf. @ 6" on center, 4 holes per row; minimum of 3" of gravel over pipes; not necessary underneath pipes. Perforated pipe shall be wrapped with ¼-inch galvanized hardware cloth
oncrete (if	MSHA Mix No. 3; f° <sub>c</sub> = 3500 psi @ 28 days, normal weight, air-entrained; reinforcing to meet ASTM-615-60	n/a	on-site testing of poured-in-place concrete required: 28 day strength and slump test; all concrete design (cast-in-place or pre-cast) <i>not using previously approved State or local standards</i> requires design drawings sealed and approved by a professional structural engineer licensed in the State of Maryland - design to include meeting ACI Code 350.R/89; vertical loading [H-10 or H-20]; allowable horizontal loading (based on soil pressures); and analysis of potential cracking
	AASHTO-M-6 or ASTM-C-33	0.02" to 0.04"	Sand substitutions such as Diabase and Graystone ( <b>AASHTO</b> ) #10 are not acceptable. No calcium carbonated or dolomitic sand substitutions are acceptable. No "rock dust" can be used for sand

#### Hammer Wt. 140 Lbs. Hole Diameter 8 Foreman W.R. 14133 5 Ft. Hammer Drop 30 In. Rock Core Dia. K Inspector Pipe Size 2 700 In. Boring Method 1131 Date Completed 3 / 99 / 21 Date Started 3 9 2 | Pipe Size 2 20 In. Boring Method HSA Date Completed 3 9 2 SOIL DESCRIPTION ELEV. Color, Moistura, Density, Plasticity, Size DEPTH SCALE COL Ba & Tome Damp to we? 15 16" T) Topso! 1:2" BROWN DE BROWN 3 Soft CLAY wis Rooks i 1 sme soft STET wis f 22" @ 1:4" TAR & OTANGE, MOISI SANO Dense, f- M some u/s 7.0' possible perchack Bry & Brown, Moist 7.0 St. Fr, CLM W/S Bo Hon of hole 3) comes & 4:8" B. How of hole 5wm-14 1) offset borns 5.0' NERTH 5" pipe @ 3.0 1) filled with 2.0' of 1400 O - DISINTEGRATED AT COMPLETION \( \frac{y'-y'}{f} \), HSA - HOLLOW STEM AUGERS 1 - INTACT 1 - UNDISTURBED AFTER \( \frac{HRS.}{HRS.} \) FT. CFA - CONTINUOUS FLIGHT AUGERS 1 - LOST AFTER 24 HRS. \( \frac{FT.}{FT.} \) MD - MUD DRILLING OS - DRIVEN SPLIT SPOON PT - PRESSED SHELBY TUBE CA - CONTINUOUS FLIGHT AUGER PC - ROCK CORE D - DISINTEGRATED I - INTACT AFTER HRS. FT. CFA - CONTINUOUS FLIGHT AUGERS CFA - CONTINUOUS STANDARD PENETRATION TEST-DRIVING 2" OD SAMPLER 1" WITH 140# HAMMER FALLING 30"; COUNT MADE AT 6" INTERVALS STANDARD PENETRATION TEST-DRIVING 2" OD SAMPLER 1' WITH 140# HAMMER FALLING 30"; COUNT MADE AT 6" INTERVALS

RECORD OF SOIL EXPLORATION

#### RECORD OF SOIL EXPLORATION Projects Name BROMONECK TRAIL Phase 1335 Datum Hammer Wt. / 40 Lbs. Hole Diameter 8 Foreman W. R. 148559 Surf. Elev. Ft. Hammer Drop 30 In. Rock Core Dia. X Inspector Date Started 3 / 10 / 21 Pipe Size 2 00 In. Boring Method 11 Date Completed 3 - 10 - 21 Datum Hammer Wt. 145 Lbs. Hole Diameter 8 Foreman w. R. MASSY Surf. Elev. 20,17 Ft. Hammer Drop 30" In. Rock Core Dia. X Inspector Date Started 3 · 10 · 21 Pipe Size 2 0 In. Boring Method MSA Date Completed 3 · 10 · 21 SOIL DESCRIPTION ELEV. Color, Moisture, Density, Plasticity, Size STRA DEPTH DEPTH SCALE Cond ELEV. Color, Moisture, Density, Plasticity, Size Dank Br, DNOR, nED S.T. 1.0' 05 10" 1) Topsoil: 8 DMK BR to BR, Amor BR & TAN, & BR & - while dailly MED SI. LA STLT W/S 7 3) (mas @ 4.1 f-M SAND Bo Hom of hole Beton of hole S.0' NW 6) Installed S. 0' of 5" pipe @ 3.0 1) filled with 2,0' of tho SAMPLE CONDITIONS GROUND WATER DEPTH SAMPLE CONDITIONS GROUND WATER DEPTH DS - DRIVEN SPLIT SPOON PT - PRESSED SHELBY TUBE CA - CONTINUOUS FLIGHT AUGER CA - CONTINUOUS FLIGHT AUGER CC - ROCK CORE D - DISINTEGRATED 1 - INTACT 1 - INTACT 1 - INTACT 2 - AFTER - HRS. - FT. CFA - CONTINUOUS FLIGHT AUGERS CFA - CONTINUOUS FLI DS - DRIVEN SPLIT SPOON PT - PRESSED SHELBY TUBE CA - CONTINUOUS FLIGHT AUGERS PC - ROCK CORE D - DISINTEGRATED I - INTACT AFTER HRS. FT. CFA - CONTINUOUS FLIGHT AUGERS CC - DRIVING CASING CFA - CONTINUOUS FLIGHT AUGERS CFA - MOD DRILLING STANDARD PENETRATION TEST-DRIVING 2" OD SAMPLER 1" WITH 140# HAMMER FALLING 30"; COUNT MADE AT 6" INTERVALS STANDARD PEVETRATION TEST-DRIVING 2" OD SAMPLER 1" WITH 140# HAMMER FALLING 30"; COUNT MADE AT 6" INTERVALS

NOTE: SEE SW-02 AND SW-07 FOR SWM BORING LOCATIONS

GP# G02018957

RECORD OF SOIL EXPLORATION

Projects Name BRONDASCIK TRAIL PLASE 18 \$ 5 Job# 16-00053.03

7.0'

Hammer Wt. 140 Lbs. Hole Diameter 8 Foreman W-R M43349

Ft. Hammer Drop 30 In. Rock Core Dia. K Inspector

-2-2-11-2 1 OS 22" 1) Topsail: 3"

@ 20

4) Sum - 2 A

offser Gerry S.O NW

5) AUGUREO TO 3.0

4) set 5'4" of

20 tho

1) TOPSOIL: 10"

while dailly

3) cares @ 4.5

5.0' NW

4) office swa-44

5) Augus 6 3. 0

(L) TOUSTAILED 5.9

of 5" pipe @

1) filled with

20' of 1kg


BORING METHOD

5" pipe @ 3.0' 7) filled with


> DWG. NO.: SWD-02


4 NORTH PARK DRIVE HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818

06/08/2023




	REVISIONS	ANNE ARUNDEL COUNTY								
NO.	DESCRIPTION	BY	DATE	DEPARTMENT OF PUBLIC WORKS						
				APPROVED	DATE	APPROVED	DATE	SCALE: AS NOT	ED	BROADNECK PENINSULA TRAIL
				DocuSigned by:	11/20/2023   08:5	9 EST figh Auty	11/17/2023   08:0	<b>ÐRA</b> WN BY:	DMT	PHASE IB & V
				CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT	
				APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>65</u> OF 116	STORMWATER MANAGEMENT
				DocuSigned by:  David C. Braun	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:3	PROJECT NO.	P504100	NOTES AND DETAILS
				ASSISTANT CHIEF ENG	GINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	. P504105	








CHIEF, RIGHT OF WAY


CONTRACT NO. P504105















## CONCRETE SLOPE - STATION 53+15 TO 53+55 NOT TO SCALE







I-1/4: OPEN BACK INLET PLAN HORIZ. SCALE 1" = 10'



SDP-05


GP# G02018957	
---------------	--

PROFESSIONAL CERTIFICATION
"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND."
MD LICENSE NUMBER: 53587

Day of the second secon	F MAR MINISTER STATE OF STATE
/	06/08/2023


		REVISIONS	ANNE ARUNDEL COUNTY							
	NO.	DESCRIPTION BY	DATE	DEPARTMENT OF P					RKS	
				APPROVED	DATE	APPROVED	DATE	SCALE: AS NOTE	D	BROADNECK PENINSULA TRAIL
				DocuSigned by:	11/20/2023   08:	59 EST Juli Autur	11/17/2023   08:0	Ð <b>RA</b> WN BY:	DMT	PHASE IB & V
				CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT	
				APPROVED	DATE	APPROVED HORIZ	SCALE 1" = 2 <b>0</b> "ATE	SHEET NO.	<u>70</u> OF 116	STORMDRAIN PROFILES
				DocuSigned by:  **Barid C. Braun**	11/17/2023   11:	56 EST Tom Burke	11/17/2023   18:3	PROJECT NO.	P504100	3 I OKIVIDRAIN PROFILES
23				ASSISTANT CHIEF ENG	INEER	CHIEF, RIGHT OF WAY	<b>/</b>	CONTRACT NO.	P504105	

		T	* WO	RK POINT (WP)	T	T	T	STANDARD		
STRUCTURE NO.	STRUCTURE TYPE	BASELINE	STATION	OFFSET	T.G./ T.S./ T.C.	INVERT IN	INVERT OUT	NUMBER	OWNERSHIP	REMARKS
I-3/1	STANDARD SINGLE TYPE K INLET	TRAIL-01	7+59.48	6.11 RT	22.75	-	20.23	MD 378.03		SHALLOW BOX
ES-2/1	STANDARD CONCRETE END SECTION	TRAIL-01	7+73.69	23.57 LT	-	-	20.00	MD 368.01	AA County	
ES-3/1	STANDARD METAL END SECTION	TRAIL-01	8+71.50 14+17.68	2.38 RT	-	-	21.63 17.00	MD 370.01	AA County	
EW-1/1	STANDARD TYPE C ENDWALL STANDARD CONCRETE END SECTION	TRAIL-01	14+17.00	3.88 RT	-	-		MD 368.01	AA County	
ES-6/1	HORIZONTAL ELLIPTICAL PIPE	TRAIL-01	14+28.09	25.90 LT	-	-	16.60	MD 369.00	AA County	
ES-5/1	STANDARD CONCRETE END SECTION	TRAIL-01	14+51.15	15.37 LT	-	-	17.00	MD 368.01	AA County	
	STANDARD CONCRETE END SECTION							MD 369.00	•	
ES-7/1	HORIZONTAL ELLIPTICAL PIPE	TRAIL-01	14+59.19	26.04 LT	-	-	16.40	1VID 369.00	AA County	
ES-4/1	STANDARD CONCRETE END SECTION	TRAIL-01	14+72.87	7.06 RT	-	-	17.15	MD 368.01	AA County	
R-1/1	TYPE D INLET	TRAIL-01	14+93.62	20.97 RT	19.83	14.17 (Subdrain)	16.67	AACo D/28		WEIR ELEVATION SET TO 19.00 WITH TRASH RACK (SEE SW-08)
I-2/1	MODIFIED OPEN BACK COG	TRAIL-01	17+54.09	5.67 RT	21.50	-	- 40.05	SEE DE-04	AA County	OHALLOW BOY
I-1/2 I-2/2	STANDARD SINGLE TYPE K INLET SHALLOW 10' COG INLET	TRAIL-01	27+30.07 28+94.75	4.3 RT 0.67 RT	20.25	-	18.25 17.83	MD 378.03 MD 374.66	AA County  AA County	SHALLOW BOX
MH-1/2	STANDARD PRECAST MANHOLE	TRAIL-01	28+92.90	6.73 LT	20.09	17.77 / 17.77	17.77	MD 384.01	AA County	
1-2/3	SHALLOW 10' COS INLET	TRAIL-01	30+40.36	0.67 RT	19.55	-	17.45	MD 374.67	AA County	
MH-1/3	STANDARD PRECAST MANHOLE	TRAIL-01	30+40.56	12.97 LT	19.70	17.33 /17.33	17.33	MD 384.01	AA County	
ES-1/3	STANDARD CONCRETE END SECTION	TRAIL-01	30+57.88	21.82 LT			17.23	MD 369.00	AA County	
E3-1/3	HORIZONTAL ELLIPTICAL PIPE	IRAIL-01	30+37.88	21.02 L1	-	-	17.23	MD 369.00	AA County	
EW-1/3	STANDARD TYPE E ENDWALL	TRAIL-01	30+99.30	11.9 LT	-	-	17.23	MD 356.01 MOD		TYPE C ENDWALL FOR 30INCH PIPE MODIFIED FOR 19X30 HERCP
EW-2/3	STANDARD TYPE C ENDWALL	TRAIL-02	40+94.42	18.29 RT	-	-	16.78	MD 355.02		HORIZONTAL ELLIPTICAL CONCRETE PIPE
EW-3/3	STANDARD SINCLE TYPE KINLET	TRAIL-02	41+48.56	12.18 RT	40.50	-	15.58	MD 354.01	AA County	
I-1/3 I-1/4	STANDARD SINGLE TYPE K INLET MODIFIED OPEN BACK COG	TRAIL-02 TRAIL-02	41+97.80 53+15.00	13.68 LT 1.67 RT	19.50 21.86	-	15.83	MD 378.03 SEE DE-04	AA County AA County	
I-1/4 ES-1/4	STANDARD CONCRETE END SECTION	TRAIL-02	54+76.74	1.67 RT 19.80 LT	- 21.00	-	18.50	MD 368.01	AA County  AA County	
1-2/4	STANDARD CONCRETE END SECTION  STANDARD SINGLE TYPE K INLET	TRAIL-02	60+25.14	24.74 LT	19.75		17.25	MD 378.03		SHALLOW BOX
ES-2/4	STANDARD CONCRETE END SECTION	TRAIL-03	60+47.27	12.47 RT	-	-	17.00	MD 368.01	AA County	
ES-4/4	STANDARD CONCRETE END SECTION	TRAIL-03	60+51.16	4.35 RT	-	-	17.00	MD 368.01	AA County	
ES-3/4	STANDARD CONCRETE END SECTION		61+20.22	10.97 RT	-	-	17.88	MD 368.01	AA County	
ES-1/5	STANDARD CONCRETE END SECTION	TRAIL-03	61+95.10	14.70 LT	-	-	18.28	MD 368.01	AA County	
ES-1/6	STANDARD CONCRETE END SECTION	TRAIL-03	73+51.37	26.15 LT	-	-	21.80	MD 368.01	AA County	
ES-2/6	STANDARD CONCRETE END SECTION	TRAIL-03	73+68.01 75+42.39	30.23 LT 19.36 LT	-	-	21.69 20.30	MD 368.01 MD 368.01	AA County AA County	
ES-3/6 ES-4/6	STANDARD CONCRETE END SECTION STANDARD CONCRETE END SECTION	TRAIL-03 TRAIL-03	75+42.39 75+42.23	19.36 LT 10.29 RT	-	-	20.30	MD 368.01	AA County  AA County	
ES-1/7	STANDARD CONCRETE END SECTION	BHP	610+96.71	2.99 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-2/7	STANDARD CONCRETE END SECTION	BHP	610+92.43	14.08 LT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-3/7	STANDARD CONCRETE END SECTION	ВНР	608+58.30	3.80 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-4/7	STANDARD CONCRETE END SECTION	ВНР	608+58.30	13.80 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
I-1/9	STANDARD SINGLE TYPE K INLET	TRAIL-04	97+33.74	9.57 RT	18.61	-	15.11	MD 378.03	AA County	
MH-1/9	STANDARD PRECAST MANHOLE	TRAIL-04	97+40.99	22.37 RT	19.82	15.06	14.96	MD 384.01	AA County	
I-3/9	STANDARD TYPE S COMBINATION	TRAIL-04	502+57.85	0.67 RT	17.92	12.93 / 12.66	12.41	MD 379.04	AA County	
EW-1/9	INLET DOUBLE GRATE	TDAIL 04	502+53.11	23.08 LT			FIELD VERIFY*	MD 360.01	MDOT SHA	MDOT SHA OWNS AND WILL MAINTAIN EX. 24" RCP CROSSING
	STANDARD TYPE G ENDWALL STANDARD TYPE S COMBINATION	TRAIL-04			-	-				MIDOT SHA OWNS AND WILL MAINTAIN EX. 24 RCP CROSSING
I-5/9	INLET DOUBLE GRATE	TRAIL-04	504+97.00	0.67 RT	16.41	-	13.40	MD 379.04	AA County	SHALLOW BOX
1.0/0	STANDARD TYPE S COMBINATION		500.00.00	0.07 DT	11.05		40.57	NAD 070 04		
I-6/9	INLET DOUBLE GRATE	TRAIL-04	506+96.36	0.67 RT	14.95	-	10.57	MD 379.04	AA County	
I-1/10	STANDARD TYPE S COMBINATION	TRAIL-04	508+96.36	0.67 RT	13.51	8.63	8.37	MD 379.04	AA County	
1-1/10	INLET DOUBLE GRATE	TIVALE-04	000100.00	0.07	10.01	0.00	0.07	WIB 07 0.0 T	7 to County	
I-2/10	STANDARD TYPE S COMBINATION	TRAIL-04	510+96.36	0.67 RT	12.07	6.43	6.33	MD 379.04	AA County	
MH-1/10	INLET DOUBLE GRATE PRECAST MANHOLE WITH DOGHOUSE	TRAIL-04	512+02.06	7.21 RT	11.29	5.98 / 5.38 / 1.00	0.92	SEE DE-06	AA County	MD 384.05 MANHOLE TOP WITH DOGHOUSE BASE
	STANDARD TYPE S COMBINATION									MD 304.03 MANHOLL TOP WITH DOGHOUSE BASE
I-3/10	INLET DOUBLE GRATE	TRAIL-04	512+12.71	0.67 RT	11.50	6.16	6.06	MD 379.04	AA County	
1.4/40	STANDARD TYPE S COMBINATION	TDAIL 04	E12   02 22	0.67 DT	44.00	6.70	6.60	MD 270 04	ΛΛ C - · · · - t -	
I-4/10	INLET DOUBLE GRATE	TRAIL-04	513+02.36	0.67 RT	11.90	6.79	6.69	MD 379.04	AA County	
I-5/10	STANDARD TYPE S COMBINATION	TRAIL-04	515+02.36	0.67 RT	13.00	7.90	7.65	d	AA County	
1 0/10	INLET DOUBLE GRATE	7.VAIL-V7	1.5.52.55	5.01	15.55	1.55	1.00	~	Coding	
I-6/10	STANDARD TYPE S COMBINATION	TRAIL-04	517+02.36	0.67 RT	14.25	9.71	9.61	MD 379.04	AA County	
	INLET DOUBLE GRATE					1				<u> </u>
I-7/10	STANDARD TYPE S COMBINATION INLET DOUBLE GRATE	TRAIL-04	519+03.00	0.67 RT	15.75	-	11.13	MD 379.04	AA County	
ES-2/12	STANDARD CONCRETE END SECTION	SPSP-01	305+46.46	12.21 RT	-	_	FIELD VERIFY*	MD 368.01	AA County	
ES-1/12	STANDARD CONCRETE END SECTION	SPSP-01	305+73.46	23.63 LT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-1/13	STANDARD CONCRETE END SECTION	SPSP-01	320+83.15	13.64 LT	-	-	FIELD VERIFY*	MD 368.01		CENTER END SECTION IN STREAM
ES-2/13	STANDARD CONCRETE END SECTION	SPSP-01	320+84.66	4.40 RT	-	-	FIELD VERIFY*	MD 368.01		CENTER END SECTION IN STREAM
ES-3/13	STANDARD CONCRETE END SECTION	SPSP-01	320+77.41	13.13 LT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-4/13	STANDARD CONCRETE END SECTION	SPSP-01	320+79.89	4.80 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-1/14	STANDARD CONCRETE END SECTION	SPSP-01	350+26.15 350+26.57	14.00 RT 4.00 LT	-	-	FIELD VERIFY*	MD 368.01 MD 368.01	AA County	
ES-2/14 ES-5/15	STANDARD CONCRETE END SECTION STANDARD METAL END SECTION	SPSP-01 SPSP-01	350+26.57 331+92.76	4.00 LT 13.63 LT	-	-	FIELD VERIFY* FIELD VERIFY*	MD 368.01 MD 370.01	AA County AA County	
ES-6/15	STANDARD METAL END SECTION  STANDARD METAL END SECTION	SPSP-01	331+94.28	7.04 RT		1	FIELD VERIFY*	MD 370.01	AA County  AA County	
ES-3/15	STANDARD CONCRETE END SECTION	SPSP-01	333+38.64	14.25 LT	-	-	FIELD VERIFY*	MD 368.01	AA County	<del> </del>
ES-4/15	STANDARD CONCRETE END SECTION	SPSP-01	333+38.13	3.75 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-7/15	STANDARD CONCRETE END SECTION	SPSP-01	338+66.99	3.80 RT		1	FIELD VERIFY*	MD 368.01	AA County	
ES-8/15	STANDARD CONCRETE END SECTION	SPSP-01	338+66.99	14.25 LT			FIELD VERIFY*	MD 368.01	AA County	
ES-2/15	STANDARD CONCRETE END SECTION	SPSP-01	339+60.31	16.92 LT	-	-	FIELD VERIFY*	MD 368.01	AA County	
ES-1/15	STANDARD CONCRETE END SECTION	SPSP-01	340+12.03	5.03 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
F2 2//-	STANDARD CONCRETE END SECTION	0005.5	244.00.00	45.54	-	-		NAD COC C:	A A . O =	
ES-9/15	HORIZONTAL ELLIPTICAL PIPE	SPSP-01	341+30.30	15.51 LT		1	FIELD VERIFY*	MD 368.01	AA County	
ES-10/15	STANDARD CONCRETE END SECTION HORIZONTAL ELLIPTICAL PIPE	SPSP-01	341+30.30	7.30 RT	-	-	FIELD VERIFY*	MD 368.01	AA County	
L3-10/13	HOMEONIAL LLLIF HOAL FIFE	3F 3F -U1	UT1100.00	1.00 111			I ILLD VEINET	ו ט.טט בוויו	AA County	<u> </u>



#### WORKPOINT LOCATIONS NOT TO SCALE

WORK POINT LOCATIONS FOR STRUCTURES ARE SHOWN IN THE DIAGRAMS ABOVE. THE TOP ELEVATIONS OF THE STRUCTURES ARE GIVEN AT THE WORK POINTS. FOR CURB INLETS AND COMBINATION INLETS (TYPE S-INLET), THE TOP ELEVATIONS ARE GIVEN AT THE TOP OF CURB.




NOT TO SCALE


DWG. NO.:


AECOM 4 NORTH PARK DRIVE SUITE 300 HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818

PROFESSIONAL CERTIFICATION "I CERTIFY THAT THESE DOCUMENTS
WERE PREPARED OR APPROVED BY
ME, AND THAT I AM A DULY LICENSED
PROFESSIONAL ENGINEER UNDER
THE LAWS OF THE STATE OF
MARYLAND." MD LICENSE NUMBER: 53587




										GP# G02018957	DWG. NO.: DS-01
	REVISIONS	ANNE ARUNDEL COUNTY									
NO.	DESCRIPTION	BY	DATE								
				APPROVED	DATE	APPROVED	DATE	SCALE: AS NOTE	D	BROADNECK PENINSU	JLA TRAIL
3				Docusigned by:	11/20/2023   08:5	59 EST ful autur	11/17/2023   08:0	DRAWN BY:	DMT	PHASE IB & V	
				CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT		_
				APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>71</u> OF 116	DRAINAGE SCHE	EDULES
				DocuSigned by:  **David C. Braun**	11/17/2023   11:5	56 EST Tom Burke	11/17/2023   18:	PROJECT NO.	P504100	AND DETAIL	LS
3				ASSISTANT CHIEF EN	IGINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	P504105		_





- (A) 24 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR STOP LINE
- B) 12 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR CROSSWALK



## NOTES:

- I. CURB, RAMP, AND SIDEWALK ELEVATIONS PROVIDED ARE FOR CONTRACTOR REFERENCE ONLY.

  ACTUAL FIELD CONDITIONS MAY VARY. PRIOR TO CONSTRUCTION, THESE ELEVATIONS SHALL


  BE CONFIRMED BY THE CONTRACTOR TO MEET THE REQUIREMENTS SET FORTH BY THE LATEST

  EDITION OF THE AMERICANS WITH DISABILITIES ACT AND THE MARYLAND STATE HIGHWAY


  ADMINISTRATION'S (MDSHA) "ACCESSIBILITY POLICY AND GUIDELINES FOR PEDESTRIAN FACILITIES ALONG

  STATE HIGHWAY (2010)." ANY DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER.
- 2. PROPOSED CURB/GUTTER AND SIDEWALK TIE-INS SHALL BE MADE TO THE NEAREST EXISTING CONCRETE JOINT WHEN POSSIBLE.
- 3. ALL SIDEWALK RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH MARYLAND STATE HIGHWAY ADMINISTRATION (MDSHA) STANDARD DETAILS, INCLUDING MD 655.11 AND MD 655.12. SEE DWG. NO. DE-OI.

POINT TABLE											
POINT	BASELINE	STATION	OFFSET	NORTHING	EASTING	ELEVATION					
100	TRAIL 01	30+78.62	32.97 LT	495,666.81	1,471,810.21	MATCH EX					
101	TRAIL 01	30+78.50	28.33 LT	495,662.26	1,471,809.28	20.04					
102	TRAIL 01	30+41.81	7.12 RT	495,633.81	1,471,766.93	18.90					
103	TRAIL 02	40+07.38	26.92 LT	495,660.88	1,471,843.93	MATCH EX					
104	TRAIL 02	40+07.84	18.95 RT	495,623.69	1,471,870.80	MATCH EX					
105	TRAIL 02	40+33.79	8.00 LT	495,655.68	1,471,882.89	20.80					
106	TRAIL 02	40+36.89	17.18 LT	495,665.12	1,471,885.07	MATCH EX					
A1	TRAIL 01	30+63.99	2.69 LT	495,639.57	1,471,790.49	19.90					
A2	TRAIL 01	30+69.44	7.26 LT	495,643.11	1,471,796.66	19.60					
A3	TRAIL 01	30+75.21	17.64 LT	495,652.31	1,471,804.16	19.80					
A4	TRAIL 01	30+75.28	20.09 LT	495,654.71	1,471,804.66	20.35					
A5	TRAIL 01	30+65.14	21.16 LT	495,657.55	1,471,794.87	20.02					
A6	TRAIL 01	30+61.13	13.95 LT	495,651.15	1,471,789.65	19.72					
A7	TRAIL 01	30+57.64	10.42 LT	495,648.29	1,471,785.59	20.15					
B1	TRAIL 02	40+00.25	10.00 LT	495,642.95	1,471,847.88	20.10					
B2	E COLLEGE PKWY	127+49.32	34.78 LT	495,640.74	1,471,848.22	19.70					
B3	E COLLEGE PKWY	127+55.14	29.31 LT	495,634.25	1,471,852.90	19.55					
B4	TRAIL 02	40+02.28	7.79 RT	495,629.59	1,471,859.81	19.90					
B5	TRAIL 02	40+09.57	4.50 RT	495,636.49	1,471,863.87	20.02					
B6	TRAIL 02	40+08.12	0.00 RT	495,639.32	1,471,860.08	19.70					
B7	TRAIL 02	40+13.12	0.00 RT	495,642.21	1,471,864.16	20.30					
B8	TRAIL 02	40+13.12	8.00 LT	495,648.74	1,471,859.54	20.42					



DETAIL 'A'
SCALE 1"=5'




DWG. NO.:


GP# G02018957

	AECOM 4 NORTH PARK DRIVE
AECOM	SUITE 300 HUNT VALLEY, MARYLAND 21030 PHONE: 410-785-7220 FAX: 410-785-6818

PROFESSIONAL CERTIFICATION
"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND."
MD LICENSE NUMBER: 53587




	REVISIONS							ANNE ARUND	EL COUNTY		
	NO.	DESCRIPTION	BY	DATE			RKS				
					APPROVED	DATE	APPROVED	DATE	SCALE: AS NOTE	D	BROADNECK PENINSULA TRAIL
5					Docusigned by:	11/20/2023   08:5	9 EST Juli Auty	11/17/2023   08:0	DRAWN BY:	DMT	PHASE IB & V
					CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT	
					APPROVED	DATE	APPROVED	DATE	SHEET NO.	<u>72</u> OF 116	INTERSECTION DETAIL
					DocuSigned by:  David C. Braun	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:3	PESTECT NO.	P504100	INTERSECTION DETAIL
3					ASSISTANT CHIEF ENG	GINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	P504105	



	POINT TABLE												
POINT	BASELINE	STATION	OFFSET	NORTHING	EASTING	<b>ELEVATION</b>							
201	TRAIL 02	55+23.30	2.00 RT	495,293.44	1,473,306.48	MATCH EX							
202	TRAIL 02	54+48.91	2.00 RT	495,270.21	1,473,238.38	22.08							
203	TRAIL 02	53+70.30	2.00 RT	495,293.04	1,473,163.17	21.85							
204	TRAIL 02	53+58.98	2.00 RT	495,297.66	1,473,152.37	21.82							
205	TRAIL 02	53+55.18	2.00 RT	495,299.75	1,473,149.01	21.80							
206	TRAIL 03	60+12.79	36.98 LT	495,295.91	1,473,333.70	MATCH EX.							
207	TRAIL 03	60+06.73	31.33 LT	495,289.15	1,473,328.91	21.26							
208	TRAIL 03	60+09.00	16.42 RT	495,242.84	1,473,340.79	MATCH EX.							
C1	TRAIL 02	54+83.35	0.00	495,271.86	1,473,272.93	22.41							
C2	TRAIL 02	54+89.91	0.67 RT	495,273.41	1,473,279.36	21.87							
C3	TRAIL 02	54+99.19	0.67 RT	495,277.67	1,473,287.72	21.75							
C4	TRAIL 02	55+01.19	0.00 RT	495,279.31	1,473,289.06	22.22							
C5	TRAIL 02	54+99.19	8.00 LT	495,285.06	1,473,283.19	21.87							
C6	TRAIL 02	54+89.91	8.00 LT	495,281.42	1,473,276.04	22.00							
C7	TRAIL 02	54+83.35	8.00 LT	495,279.54	1,473,270.70	22.53							
D1	E COLLEGE PKWY	142+67.97	38.57 LT	495,272.64	1,473,325.18	22.52							
D2	E COLLEGE PKWY	142.69.47	32.63 LT	495,266.52	1,473,324.81	22.25							
D3	E COLLEGE PKWY	142+75.38	24.48 RT	495,256.96	1,473,327.97	22.60							
D4	TRAIL 03	60+02.30	5.53 RT	495,252.15	1,473,332.02	23.16							
D5	TRAIL 03	60+06.00	0.00	495,258.32	1,473,334.53	22.72							
D6	TRAIL 03	60+06.00	10.00 LT	495,268.11	1,473,332.51	22.84							

- A 24 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR STOP LINE
- B 12 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR CROSSWALK
- C NOSE DOWN CURB (MAX. 3:1 SLOPE)



GP# G02018957

DWG. NO.: ID-02

PROFESSIONAL CERTIFICATION "I CERTIFY THAT THESE DOCUMENTS
WERE PREPARED OR APPROVED BY
ME, AND THAT I AM A DULY LICENSED
PROFESSIONAL ENGINEER UNDER
THE LAWS OF THE STATE OF
MARYLAND." AECOM
4 NORTH PARK DRIVE
SUITE 300
HUNT VALLEY, MARYLAND 21030
PHONE: 410-785-7220
FAX: 410-785-6818 MD LICENSE NUMBER: 53587

EXPIRATION DATE: 12-09-2024

06/08/2023

S	REVISIONS		
BY DATE	DESCRIPTION BY		
		APPROVED DATE APPROVED	
		Docusigned by: 11/20/2023   08:59 EST full Autry	
		CHIEF ENGINEER PROJECT MAN	ÑΑ
		APPROVED DATE APPROVED	
		Docusigned by:  David C. Braun  11/17/2023   11:56 EST Docusioned by:  Dom Burlet	
		ASSISTANT CHIEF ENGINEER CHIEF, RIGHT	OI


DEPARTMENT OF PUBLIC WORKS DATE | SCALE: AS NOTED BROADNECK PENINSULA TRAIL PHASE IB & V 11/17/2023 | 08:0 DRAWN BY: PROJECT MANAGER CHECKED BY: DMT DATE SHEET NO. <u>73</u> OF 116 11/17/2023 | 18:3 PESTECT NO. P504100

CONTRACT NO. P504105

ANNE ARUNDEL COUNTY


CHIEF, RIGHT OF WAY

INTERSECTION DETAIL



	POINT TABLE												
POINT	BASELINE	STATION	OFFSET	NORTHING	EASTING	<b>ELEVATION</b>							
301	TRAIL 03	84+37.13	20.55 LT	494,522.48	1,475,613.31	MATCH EX.							
302	TRAIL 03	84+27.02	18.72 RT	494,502.70	1,475,577.92	23.40							
303	TRAIL 03	84+23.49	21.21 RT	494,503.53	1,475,573.68	MATCH EX.							
304	TRAIL 04	90+00.93	27.17 LT	494,517.36	1,475,645.66	MATCH EX.							
305	TRAIL 04	90+10.86	16.17 RT	494,477.60	1,475,665.58	23.35							
306	TRAIL 04	90+27.65	26.61 RT	494,471.43	1,475,684.37	MATCH EX.							
E1	E COLLEGE PKWY	166+61.80	21.72 LT	494,505.60	1,475,593.20	23.70							
E2	E COLLEGE PKWY	166+66.82	25.43 LT	494,507.57	1,475,599.14	23.12							
E3	E COLLEGE PKWY	166+72.10	33.95 LT	494,514.01	1,475,606.81	23.00							
E4	TRAIL 03	84+36.86	15.86 LT	494,519.44	1,475,609.73	23.43							
E5	TRAIL 03	84+30.20	10.00 LT	494,520.22	1,475,600.90	23.43							
E6	TRAIL 03	84+30.20	0.00	494,513.31	1,475,593.66	23.28							
F1	E COLLEGE PKWY	167+11.92	38.52 LT	494,505.92	1,475,646.06	23.25							
F2	E COLLEGE PKWY	167+14.06	32.82 LT	494,499.84	1,475,646.32	22.85							
F3	E COLLEGE PKWY	167+20.93	25.32 LT	494,490.57	1,475,650.51	23.13							
F4	TRAIL 04	90+02.69	5.35 RT	494,486.18	1,475,655.08	23.79							
F5	TRAIL 04	90+06.00	0.00	494,492.16	1,475,657.03	23.25							
F6	TRAIL 04	90+06.00	10.00 LT	494,501.88	1,475,654.66	23.40							

- A 24 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR STOP LINE
- B 12 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR CROSSWALK
- C NOSE DOWN CURB (MAX. 3:1 SLOPE)



GP# G02018957

BROADNECK PENINSULA TRAIL PHASE IB & V

INTERSECTION DETAIL

DWG. NO.:

ID-03


"I CERTIFY THAT THESE DOCUMENTS
WERE PREPARED OR APPROVED BY
ME, AND THAT I AM A DULY LICENSED
PROFESSIONAL ENGINEER UNDER
THE LAWS OF THE STATE OF
MARYLAND." AECOM
4 NORTH PARK DRIVE
SUITE 300
HUNT VALLEY, MARYLAND 21030
PHONE: 410-785-7220
FAX: 410-785-6818 MD LICENSE NUMBER: 53587


EXPIRATION DATE: 12-09-2024

06/08/2023

11/2	NO.	DESC
2=		
Zi E		
### E		
illi		
€00		
3/2023		


	REVISIONS						ANNE ARUNI	DEL COUNTY		
0.	DESCRIPTION	BY	DATE				DEPARTMENT OF	PUBLIC WOF	 RKS	
				APPROVED	DATE	APPROVED	DATE	SCALE: AS NOTE	.D	
				Docusigned by:	11/20/2023   08:5	9 EST Juli Autus	11/17/2023   08:0	DRAWN BY:	DMT	
				CHIEF ENGINEER	_	PROJECT MANAGER		CHECKED BY:	DMT	
				APPROVED	DATE	APPROVED	DATE	SHEET NO.	74_OF 116	
				DocuSigned by:  **David C. Braun**	11/17/2023   11:5	6 EST Down Burke	11/17/2023   18:	3 <b>₽Æ9J</b> ECT NO.	P504100	
				ASSISTANT CHIEF ENGI	NEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	P504105	





	POINT TABLE												
POINT	BASELINE	STATION	OFFSET	NORTHING	EASTING	ELEVATION							
401	TRAIL 04 CURB	521+41.50	2.00 RT	493,607.74	1,478,408.54	MATCH EX							
402	TRAIL 04 CURB	521+00.16	0.67 RT	493,585.34	1,478,374.90	MATCH EX.							
403	TRAIL 04 CURB	520+94.30	0.67 RT	493,585.77	1,478,368.96	MATCH EX.							
404	TRAIL 04 CURB	520+89.30	2.00 RT	493,585.66	1,478,363.60	17.02							
405	E COLLEGE PKWY	196+41.78	55.68 LT	493,603.52	1,478,432.21	MATCH EX.							
406	SPSP 01	521+32.00	77.51 RT	493,554.38	1,478,464.79	MATCH EX.							
G1	TRAIL 04 CURB	520+90.12	0.00 RT	493,587.34	1,478,364.98	17.54							
G2	TRAIL 04 CURB	521+01.91	0.00 RT	493,586.07	1,478,376.65	17.67							
G3	TRAIL 04 CURB	521+08.93	0.67 RT	493,586.59	1,478,383.74	17.38							
G4	TRAIL 04 CURB	521+20.64	0.67 RT	493,591.63	1,478,394.49	17.55							
G5	TRAIL 04 CURB	521+22.64	0.00 RT	493,593.37	1,478,395.71	18.08							
G6	TRAIL 04 CURB	521+20.64	10.00 LT	493,600.38	1,478,388.38	17.70							
G7	TRAIL 04 CURB	521+08.93	10.00 LT	493,596.87	1,478,380.91	17.53							
G8	TRAIL 04 CURB	521+01.91	10.00 LT	493,596.05	1,478,376.01	17.82							
G9	TRAIL 04 CURB	520+90.45	10.00 LT	493,596.88	1,478,367.97	17.69							
H1	SPSP 01	521+35.65	37.06 RT	493,584.59	1,478,436.26	17.87							
H2	SPSP 01	521+33.75	41.53 RT	493,578.78	1,478,437.94	17.20							
НЗ	SPSP 01	521+32.09	50.89 RT	493,570.26	1,478,443.42	16.92							
H4	SPSP 01	521+31.89	57.13 RT	493,566.17	1,478,448.17	17.23							
H5	SPSP 01	521+34.32	54.48 RT	493,572.92	1,478,449.56	17.15							
H6	SPSP 01	521+36.72	46.42 RT	493,582.10	1,478,445.59	17.30							

- A 24 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR STOP LINE
- B 12 INCH WHITE HEAT APPLIED PERFORMED THERMOPLASTIC PAVEMENT MARKING FOR CROSSWALK
- C NOSE DOWN CURB (MAX. 3:1 SLOPE)




AECOM
4 NORTH PARK DRIVE
SUITE 300
HUNT VALLEY, MARYLAND 21
PHONE: 410-785-7220
FAX: 410-785-6818

PROFESSIONAL CERTIFICATION

"I CERTIFY THAT THESE DOCUMENTS WERE PREPARED OR APPROVED BY ME, AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND."

MD LICENSE NUMBER: 53587



	REVISIONS				ANNE ARUNDEL COUNTY						
	NO.	DESCRIPTION	BY	DATE	_	DEPARTMENT OF PUBLIC WORKS					
					APPROVED	DATE	APPROVED	DATE	SCALE: AS NOTE	D	BROADNECK PENINSULA TRAIL
15					DocuSigned by:	11/20/2023   08:5	9 EST Juli Autus	11/17/2023   08:0	Đ <b>RΆ</b> WN BY:	DMT	PHASE IB & V
					CHIEF ENGINEER		PROJECT MANAGER		CHECKED BY:	DMT	
					APPROVED	DATE	APPROVED	DATE	SHEET NO.	75_OF 116	INTERSECTION DETAIL
					DocuSigned by:  David C. Braun	11/17/2023   11:5	6 EST Tom Burke	11/17/2023   18:3	PROJECT NO.	P504100	INTERSECTION DETAIL
3					ASSISTANT CHIEF EN	GINEER	CHIEF, RIGHT OF WAY		CONTRACT NO.	P504105	