SHEET INDEX **DESCRIPTION** SHEET NO. DWG NO. DD01A - DD01B COVER SHEET - KEY SHEET GENERAL NOTES, LEGEND, AND ABBREVIATIONS DD02 DD03A - DD03D TYPICAL SECTIONS AND DETAILS DD04A - DD04F SITE AND GRADING PLANS DD05A - DD05G **GEOMETRY PLANS** 14-20 DD06A - DD06O TRAIL PROFILES DD07A - DD07F DRAINAGE AREA MAPS 36-41 STORMWATER MANAGEMENT PLANS DD08A - DD08S STORM DRAIN DRAINAGE AREA MAPS DD09A - DD09E STORM DRAIN PROFILES DD09F - DD09H DD10A - DD10.I SEDIMENT CONTROL PLANS DD11A - DD11H INTERSECTION DETAILS ROAD IMPROVEMENT PLANS DD12A - DD12B SIGNAL, SIGNING, AND MARKING PLAN DD13A - DD13M DD14A - DD14C MAINTENANCE OF TRAFFIC DETAILS RETAINING WALL PLANS, ELEVATIONS AND DETAILS 106-112 DD15A - DD15G **BOARDWALK ELEVATIONS AND DETAILS** DD16A - DD16G 113-119 LANDSCAPE AND TREE PRESERVATION PLANS DD17A - DD17G 120-126 TREE PROTECTION PLANS DD18A - DD18I

SEQUENCE OF CONSTRUCTION

DEMOLITION PLANS

1. NOTIFY THE DEPARTMENT OF INSPECTIONS AND PERMITS (410-222-7780) AT LEAST 48 HOURS BEFORE COMMENCING WORK. WORK MAY NOT COMMENCE UNTIL THE PERMITTEE OR THE RESPONSIBLE PERSONNEL HAVE MET ON SITE WITH THE SEDIMENT AND EROSION CONTROL INSPECTOR TO REVIEW THE APPROVED PLANS.

PHASE I - PERIMETER SEDIMENT CONTROLS

DD19A - DD19B

- 2. STAKEOUT LIMITS OF DISTURBANCE ALONG ENTIRE PROJECT AND WALK ALIGNMENT WITH PROJECT MANAGER AND PENNONI
- 3. CLEAR AND GRUB FOR THE INSTALLATION OF STABILIZED CONSTRUCTION ENTRANCES AND PERIMETER CONTROLS. CONDUCT ROOT PRUNING AS NOTED ON TREE PRESERVATION PLANS AND TREE PRESERVATION SEQUENCE OF
- 4. INSTALL STABILIZED CONSTRUCTION ENTRANCES AND PERIMETER CONTROLS. INSTALL THE PIPE SLOPE DRAINS. (3
- 5. CONTACT COUNTY INSPECTOR FOR INITIAL INSPECTION. (1 DAY)
- 6 SOME OR ALL OF THE PHASES SHOWN BELOW WILL RUN CONCURRENTLY. WITH APPROVAL OF THE INSPECTOR, CONSTRUCTION OF BOARDWALKS, ITEMS REQUIRING SAME DAY STABILIZATION AND TRAFFIC SIGNAL WORK MAY BE DONE

PHASE 2 - BAY DALE TO SHORE ACRES ROAD

- 7. UPON APPROVAL OF INSPECTOR BEGIN CLEARING AND GRADING FOR THE INSTALLATION OF TWO STAGING AREAS IMMEDIATELY WEST OF BAYDALE DRIVE. STAGING AREA SHALL BE STABILIZED WITH 6" (MIN.) OF WOODCHIP MULCH. PREFERABLY FROM MATERIAL CLEARED AND CHIPPED ON SITE. (1 WEEK)
- 8. BEGIN CLEARING FOR THE INSTALLATION OF CULVERT EXTENSIONS, STORM DRAINS, AND DRAINAGE STRUCTURES. (2 DAYS) 9. INSTALL CULVERT EXTENSIONS, STORM DRAINS, STRUCTURES AND RIP RAP. UPON INSTALLATION OF STORM DRAIN
- INSTALL INLET PROTECTION AS SHOWN ON PLANS, (1 WEEK) PIPE SLOPE DRAINS AS NEEDED DURING GRADING, MAINTAINING POSITIVE FLOW THROUGH PSD. AS SLOPES 3:1 AND GREATER ARE COMPLETED, TOPSOIL, SEED, AND PLACE PERMANENT SOIL STABILIZATION MATTING. ALL SOIL STABILIZATION MATTING SHALL BE COMPRISED OF BIODEGRADABLE MATERIAL. COMPLETE WORK WITHIN CRITICAL ROOT
- ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. (6 WEEKS) 11. CONCURRENT WITH STEP 10. CONSTRUCT RETAINING WALL A AND B. AS WALLS IN FILL ARE CONSTRUCTED, BRING GRADE UP TO ESTABLISH TRAIL SUBGRADE. ADJUST PIPE SLOPE DRAINS AS NEEDED DURING WALL CONSTRUCTION, MAINTAINING POSITIVE FLOW THROUGH PSD. WHEN FINAL GRADE AT 1110 HAS BEEN ACHIEVED DIRECT ADJACENT PSD TO 1110. COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS.
- 12. CONSTRUCT BOARDWALK AND BOARDWALK ABUTMENTS. BOARDWALKS TO BE CONSTRUCTED FROM BOARDWALK SURFACE OR TRAIL SUBGRADE; NO DISTURBANCE OR GRADING FOR BOARDWALK CONSTRUCTION IS PERMITTED. CLEARING FOR BOARDWALK SHALL BE THE MINIMUM NECESSARY FOR CONSTRUCTION. ALL TREES SHALL BE REMOVED BY HAND AND STUMPS LEFT IN PLACE WITHIN BOARDWALK FOOTPRINT. (3 WEEKS)
- 13. WITH THE ESTABLISHMENT OF TRAIL SUBGRADE, BEGIN INSTALLING STONE BASE AND ASPHALT PAVING. COMPLETE ALL WORK AT INTERSECTIONS, INCLUDING TRAFFIC SIGNAL WORK. STABILIZE DISTURBED AREAS WITH SEED AND STRAW, AND INSTALL SOIL STABILIZATION MATTING IN SWALES. (2 WEEKS)
- 14 ONCE PAVING HAS BEEN COMPLETED AND SITE PRELIMINARY STABILIZED, COMPLETE FINAL GRADING FOR THE INSTALLATION OF STORMWATER MEASURES AND INSTALL ALL STORMWATER FACILITIES. STORMWATER FACILITIES SHALL NOT BE INSTALLED UNTIL CONTRIBUTING DRAINAGE AREA IS 95% STABILIZED. IF INSPECTOR ALLOWS EARLIER INSTALLATION, PROTECT PERIMETER OF FACILITY WITH SILT FENCE, AND COVER WITH FILTER FABRIC UNTIL LANDSCAPING IS INSTALLED. (2 WEEK)
- 15. INSTALL LANDSCAPING, FENCING, AND REFORESTATION. (2 WEEKS)
- 16. WITH COMPLETION OF WORK AND STABILIZATION OF SITE, CONTACT COUNTY INSPECTOR FOR FINAL INSPECTION. WITH APPROVAL OF INSPECTOR, REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES. (1 WEEK)


PHASE 3 -SHORE ACRES ROAD TO KIMWOOD DRIVE

- 17. UPON APPROVAL OF INSPECTOR BEGIN CLEARING AND GRADING FOR THE INSTALLATION OF A STAGING AREA IMMEDIATELY WEST OF SHORE ACRES ROAD. STAGING AREA SHALL BE STABILIZED WITH 6" (MIN.) OF WOODCHIP MULCH, PREFERABLY FROM MATERIAL CLEARED AND CHIPPED ON SITE. (2 DAYS)
- 18. BEGIN CLEARING FOR THE INSTALLATION OF STORM DRAINS AND DRAINAGE STRUCTURES. (2 DAYS)
- 19. INSTALL STORM DRAINS AND RIP RAP. INSTALL INLET PROTECTION AS SHOWN ON PLANS. INSTALL EARTH DIKES AT STRUCTURE 1141. STORM DRAIN CONSTRUCTION SHALL OCCUR DURING A 3 DAY (MIN,) CLEAR WEATHER PERIOD. STABILIZE AREAS IMMEDIATELY UPON CONSTRUCTION OF STORM DRAINS. NO SEDIMENT SHALL ENTER EXISTING STORM DRAIN SYSTEMS. (2 WEEKS)
- 20.UPON COMPLETION OF STORM DRAINAGE WORK, BEGIN CLEARING AND GRADING TO ESTABLISH TRAIL SUBGRADE. COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS.
- 21. CONCURRENT WITH STEP 20, CONSTRUCT RETAINING WALL D. E. F AND N. AS WALLS IN FILL ARE CONSTRUCTED, BRING GRADE UP TO ESTABLISH TRAIL SUBGRADE. AS SLOPES 3:1 AND GREATER ARE COMPLETED, TOPSOIL, SEED, AND PLACE PERMANENT SOIL STABILIZATION MATTING. COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. (8 WEEKS)
- 22.CONSTRUCT BOARDWALKS AND BOARDWALK ABUTMENTS. BOARDWALKS TO BE CONSTRUCTED FROM BOARDWALK SURFACE OR TRAIL SUBGRADE; NO DISTURBANCE OR GRADING FOR BOARDWALK CONSTRUCTION IS PERMITTED. CLEARING FOR BOARDWALK SHALL BE THE MINIMUM NECESSARY FOR CONSTRUCTION. ALL TREES SHALL BE REMOVED BY HAND AND STUMPS LEFT IN PLACE WITHIN BOARDWALK FOOTPRINT. (8 WEEKS)
- 23. WITH THE ESTABLISHMENT OF TRAIL SUBGRADE, BEGIN INSTALLING STONE BASE AND ASPHALT PAVING. COMPLETE ALL WORK AT INTERSECTIONS INCLUDING TRAFFIC SIGNAL WORK. STABILIZE DISTURBED AREAS WITH SEED AND STRAW, AND PLACE SOIL STABILIZATION MATTING IN SWALES. (2 WEEKS)
- 24. ONCE PAVING HAS BEEN COMPLETED AND SITE PRELIMINARY STABILIZED, COMPLETE FINAL GRADING FOR THE INSTALLATION OF STORMWATER MEASURES AND INSTALL ALL STORMWATER FACILITIES. STORMWATER FACILITIES SHALL NOT BE INSTALLED UNTIL CONTRIBUTING DRAINAGE AREA IS 95% STABILIZED. IF INSPECTOR ALLOWS EARLIER INSTALLATION. PROTECT PERIMETER OF FACILITY WITH SILT FENCE, AND COVER WITH FILTER FABRIC UNTIL LANDSCAPING IS "I HEREBY CERTIFY THAT THE STORMWATER BEST MANAGEMENT PRACTICES SHOWN ON THE INSTALLED. (3 WEEKS
- 25.INSTALL LANDSCAPING, FENCING, AND REFORESTATION. (2 WEEKS)
- 26.WITH COMPLETION OF WORK AND STABILIZATION OF SITE, CONTACT COUNTY INSPECTOR FOR FINAL INSPECTION. WITH APPROVAL OF INSPECTOR, REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES. (1 WEEK)

SEQUENCE OF CONSTRUCTION CONTINUED ON SHEET 3

ANNE ARUNDEL COUNTY

DEPARTMENT OF PUBLIC WORKS BROADNECK PENINSULA TRAIL - PHASE III PROJECT No. P504100/CONTRACT No. P504104 SHA CONTRACT NO. AA 75 | B53 FA PROJECT NO. TAP-3(735)E CONSTRUCTION DOCUMENTS



OUTFALL STATEMENT

CONDITION OF THIS OUTFALL, THIS IS AN ADEQUATE OUTFALL.

THIS PROJECT HAS 15 DISTINCT OUTFALLS IN THE MAGOTHY AND SEVERN RIVER WATERSHEDS DUE TO ITS LOCATION ALONG A RIDGE WITHIN THE BROADNECK PENINSULA. THE OUTFALLS WERE INVESTIGATED BY PENNONI DURING 2017-2018. PHOTOGRAPHS OF THE OUTFALLS ARE INCLUDED IN THE

SITE OUTFALL #1 IS LOCATED AT AN EXISTING 15" CULVERT THAT CROSSES UNDER BAY DALE DRIVE AT COLLEGE PARKWAY AND DRAINS EAST TO A TRIBUTARY OF "THE MACOTHY RIVER. THIS CULVERT CONNECTS TO STORM DRAIN AND DRAINAGE IMPRROVEMENTS THAT ARE BEING INSTALLED AS PART OF BROADNECK PENINSULA TRAIL PHASE 2. THE DRAINAGE FROM PHASE 3 WAS ACCOMODATED IN THE DESIGN OF THE PHASE 2 IMPROVEMENTS. SITE OUTFALL #2 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO A TRIBUTARY OF THE SEVERN RIVER." BASED ON FIELD INVESTIGATION THIS IS A STABLE OUTFALL. STORMWATER MANAGEMENT IMPROVEMENTS AND ADDITIONAL RIP RAP ARE BEING INSTALLED AT THE UPSTREAM END OF THIS CULVERT AS PART OF THE TRAIL PROJECT. BASED ON THESE IMPROVEMENTS AND THE CURRENT

SITE OUTFALL #3 IS LOCATED AT AN EXISTING 36" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO A TRIBUTARY OF THE SEVERN RIVER." BASED ON A FIELD INVESTIGATION, THIS OUTFALL IS STABLE AT THE UPSTREAM END, BUT THE DOWNSTREAM END OF THE CULVERT IS ERODED WHERE THE CONCRETE APRON TRANSITIONS TO THE EXISTING RECEIVING CHANNEL. THIS OUTFALL WILL BE STUDIED BY THE DEPARTMENT OF PUBLIC WORKS FOR IMPROVEMENT AS PART OF A FUTURE CAPITAL PROJECT.

SITE OUTFALL #4 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO A TRIBUTARY OF THE SEVERN RIVER. BASED ON FIELD INVESTIGATION THIS IS A STABLE OUTFALL. STORMWATER MANAGEMENT IMPROVEMENTS, A BOARDWALK STRUCTURE, AND ADDITIONAL RIP RAP ARE BEING INSTALLED AT THE UPSTREAM END OF THIS CULVERT AS PART OF THE TRAIL PROJECT. BASED ON THESE IMPROVEMENTS AND THE CURRENT CONDITION OF THIS OUTFALL, THIS IS AN ADEQUATE OUTFALL.

SITE OUTFALL #5 IS LOCATED AT AN EXISTING 30" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO A TRIBUTARY OF THE SEVERN RIVER." BASED ON FIELD INVESTIGATION THIS IS A STABLE OUTFALL. STORMWATER MANAGEMENT IMPROVEMENTS AND ADDITIONAL RIP RAP ARE BEING INSTALLED AT THE UPSTREAM END OF THIS CULVERT AS PART OF THE TRAIL PROJECT. BASED ON THESE IMPROVEMENTS AND THE CURRENT CONDITION OF THIS OUTFALL, THIS IS AN ADEQUATE OUTFALL.

SITE OUTFALL #6 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO A TRIBUTARY OF THE SEVERN RIVER." THIS OUTFALL IS STABLE AT THE UPSTREAM END, BUT IS BEGINNING TO EXPERIENCE SOME CHANNEL EROSION DOWNSTREAM OF THE CULVERT. THIS OUTFALL WILL BE STUDIED BY THE DEPARTMENT OF PUBLIC WORKS FOR IMPROVEMENT AS PART OF A FUTURE CAPITAL PROJECT.

SITE OUTFALL #7 IS LOCATED AT AN EXISTING 27" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS NORTH TO FORKED CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS OUTFALL IS SEVERELY ERODED. IMPACTS BY THE TRAIL ARE MINIMIZED THROUGH THE USE OF A BOARDWALK

LOCATION PLAN

PROFESSIONAL CERTIFICATION: I, ___JAMES. A RUFF, PE ___, CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY OR APPROVED BY ME AND THAT I AM A DULY

LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE # ______ EXPIRATION DATE _____ 11/10/2021

SCALE: 1" = 1.000' STRUCTURE AND STORMWATER MANAGEMENT PRACTICES. THIS OUTFALL WILL BE STUDIED BY THE DEPARTMENT OF PUBLIC WORKS FOR IMPROVEMENT AS PART OF A FUTURE CAPITAL PROJECT.

SITE OUTFALL #8 IS LOCATED AT THE OUTFALL OF SEVERAL EXISTING CULVERTS AND A CONCRETE CHANNEL AND DRAINS NORTH TO FORKED CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS OUTFALL IS BEGINNING TO EXPERIENCE EROSION. IMPACTS BY THE TRAIL ARE MINIMIZED THROUGH THE USE OF A BOARDWALK STRUCTURE AND STORMWATER MANAGEMENT PRACTICES. THIS OUTFALL WILL BE STUDIED BY THE DEPARTMENT OF PUBLIC WORKS FOR IMPROVEMENT AS PART OF A FUTURE CAPITAL PROJECT

SITE OUTFALL #9 IS LOCATED AT AN EXISTING 24" STORM DRAIN THAT CROSSES UNDER COLLEGE PARKWAY AND CONNECTS SOUTH TO AN EXISTING STORM DRAIN SYSTEM DISCHARGING INTO MILL CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS IS A STABLE OUTFALL.

SITE OUTFALL #10 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER JONES STATION ROAD (EAST) AT COLLEGE PARKWAY AND DRAINS WEST TO AN EXISTING SWALE THAT DISCHARGES INTO MILL CREEK. A TRIBUTARY OF THE MAGOTHY RIVER. BASED ON FIELD INVESTIGATIONS. THIS IS A STABLE OUTFALL. STORMWATER MANAGEMENT IMPROVEMENTS AND ADDITIONAL RIP RAP ARE BEING INSTALLED AT THE DOWNSTREAM END OF A PROPOSED CULVERT AS PART OF THE TRAIL PROJECT. BASED ON THESE IMPROVEMENTS AND THE CURRENT CONDITION OF THIS OUTFALL, THIS IS AN ADEQUATE OUTFALL. SITE OUTFALL #11 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO AN EXISTING OPEN CHANNEL SYSTEM DISCHARGING INTO MILL CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS OUTFALL IS STABLE AT THE UPSTREAM END OF THE CULVERT BUT IS EXPERIENCING SEVERE EROSION AT THE DOWNSTREAM END WHERE THE CONCRETE CHANNEL TRANSITIONS TO A NATURAL STREAM CHANNEL. THIS OUTFALL WILL BE STUDIED BY THE DEPARTMENT OF PUBLIC WORKS FOR IMPROVEMENT AS PART OF A FUTURE CAPITAL PROJECT.

SITE OUTFALL #12 IS LOCATED AT AN EXISTING 24" CULVERT THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS SOUTH TO AN EXISTING OPEN CHANNEL SYSTEM DISCHARGING INTO MILL CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. BASED ON FIELD INVESTIGATIONS, THIS IS A STABLE OUTFALL. STORMWATER MANAGEMENT IMPROVEMENTS ARE BEING INSTALLED AS PART OF THE TRAIL PROJECT. BASED ON THESE IMPROVEMENTS AND THE CURRENT CONDITION OF THIS OUTFALL, THIS IS AN ADEQUATE OUTFALL

SITE OUTFALL #13 IS LOCATED AT AN EXISTING 6'X12' BOX CULVERT THAT CROSSES UNDER JONES STATION ROAD (WEST) AT COLLEGE PARKWAY AND DRAINS WEST TO MILL CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS OUTFALL IS CURRENTLY BEING IMPROVED UNDER A CAPITAL PROJECT

SITE OUTFALL #14 IS LOCATED AT AN EXISTING OPEN CHANNEL SYSTEM IMMEDIATELY WEST OF A 6'X12' BOX CULVERT AND DRAINS EAST TO MILL CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. BASED ON FIELD INVESTIGATIONS. THIS IS A STABLE OUTFALL.

SITE OUTFALL #15 IS LOCATED AT AN EXISTING 15" STORM DRAIN SYSTEM THAT CROSSES UNDER COLLEGE PARKWAY AND DRAINS NORTH TO AN EXISTING OPEN CHANNEL SYSTEM DICHARGING INTO DIVIDING CREEK, A TRIBUTARY OF THE MAGOTHY RIVER. THIS IS A STABLE OUTFALL.

PENNONI ASSOCIATES INC.

8890 McGaw Road, Suite 100

Columbia, MD 21045

T 410.997.8900 F 410.997.9282

ENGINEER/LANDSCAPE

ARCHITECT PENNONI ASSOCIATES, INC. 8818 CENTRE PARK DRIVE, SUITE 200 COLUMBIA MD, 21045

PROJECT LOCATION:

COLLEGE PARKWAY FROM BAY DALE DRIVE TO PENINSULA FARM ROAD ARNOLD, MD 21012 TAX ID: 300090016635

OWNER/DEVELOPER:

ANNE ARUNDEL COUNTY DEPARTMENT OF RECREATION AND PARKS AND ANNE ARUNDEL COUNTY DEPARTMENT OF PUBLIC WORKS 44 CALVERT STREET ANNAPOLIS, MD 21401 (410) 222-7000

STANDARD RESPONSIBILITY NOTES


- I(We) certify that:
- All development and construction will be done in accordance with this sediment and erosion control plan, and further, authorize the right of entry for periodic on-site evaluation by the Anne Arundel Soil Conservation District AASCD Board of Supervisors or their authorized agents. Any responsible personnel involved in the construction project will have a certificate of attendance from the Maryland Department of the Environment's approved training program for the control of sediment and erosion before beginning the project.
- If applicable, the appropriate enclosure will be constructed and maintained on sediment basin(s) included in this plan. Such structure(s) will
- The developer is responsible for the acquisition of all easements, right, and/or rights-of-way that may be required for the sediment and erosion control practices, storm water management practices and the discharge of storm water onto or across adjacent or downstream
- For initial soil disturbance or re-disturbance, permanent and/or temporary stabilization per the AASCD Vegetative Establishment shall be completed within three calendar days for the surface of all controls, dikes, swales, ditches, perimeter slopes and all slopes greater than 3 horizontal to 1 vertical (3:1); and seven days for all other disturbed or graded areas on the project site.
- 4. The grading and sediment control approval on this plan extends only to those areas within the limits of disturbance
- 5. The approval of this plan for sediment and erosion control does not relieve the developer/consultant from complying with Federal. State of
- 6. The developer must request that the sediment and erosion control inspector approve work completed in accordance with the approved erosion and sediment control plan, the grading or building permit, and the ordinance.
- All material shall be taken to a site with an approved sediment and erosion control plan
- First phase inspection and approval of the sediment and erosion control inspector shall be required upon completion of the installation of erosion and sediment controls prior to proceeding with any other earth disturbance or grading. Other building or grading inspection approvals may not be authorized until the initial approval by the sediment and erosion control inspector is given. Inspection and Permits may also require that an inspection and certification of the installation of sediment control also be performed by a design professional prior
- Approval from the inspector must be requested on final stabilization of all sites prior to removal of sediment and erosion controls
- Existing topography must be field verified by responsible personnel to the satisfaction of the sediment control inspector prior to commencing

SIGNATURE OF APPLICANT/DEVELOPER	DMTE
DAMD BRAUN	
NAME	
ENGINEER ADMINISTRATOR	
TITLE	
A A COUNTY DPW.\ BUREAU OF ENGINEERING	
AFFIL ATION	
2662 RIVA ROAD, ANNAPOUS, MD 21401	
ADDRESS	
410-222-750C	
TELEPHONE NUMBER	
pwbrcu78@aacounty.org	

CONSULTANT'S CERTIFICATION

PREPARED IN ACCORDANCE WITH THE REQUIREMENTS OF THE AASCD PLAN SUBMITTAL GUIDELINES AND THE CURRENT MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL. I HAVE REVIEWED THIS EROSION AND SEDIMENT CONTROL PLAN WITH THE OWNER/DEVELOPER.

MD P.E. LICENSE # 21774 JAMES A. RUFF, PE NAME PENNONI ASSOCIATES INC. 8818 CENTRE PARK DR., SUITE 200 CITY COLUMBIA STATE MD ZIP CODE 21045



EXISTING UTILITIES SHOWN ON THIS PLAN SET WERE DRAWN USING EXISTING RECORD DRAWINGS AND BASE FILES FROM THE UTILITY COMPANIES, FROM VISIBLE MARKINGS AND FEATURES WITHIN THE PROJECT LIMITS, FROM FIELD SURVEYS, AND FROM LIMITED TEST PITS. UTILITIES SHOWN ARE FOR INFORMATIONAL PURPOSES ONLY. THE UTILITY INFORMATION SHOWN MAY BE INNACURATE OR INCOMPLETE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITIES WITHIN THE PROJECT LIMITS OF WORK TO HIS OWN SATISFACTION PRIOR TO THE START OF CONSTRUCTION. CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES SHALL AVOID IMPACTS TO UTILITIES, AND SHALL MAINTAIN UNINTERRUPTED UTILITY SERVICE. ANY DAMAGE INCURRED DUE TO CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY AT NO COST TO ANNE ARUNDEL COUNTY IN COORDINATION WITH THE AFFECTED UTILITY COMPANIES. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING AND TEST PITTING ALL UTILITIES, AND RELOCATING THOSE UTILITIES THAT ARE IN CONFLICT WITH THE PROJECT, OR COORDINATING WITH THE UTILITY OWNER FOR RELOCATION.

SITE ANALYSIS SUMMARY LOD/SITE AREA: 11.68 AC (508,888 SF) CUT: 26,412 CY

FILL: 15,600 CY AREA VEGETATIVELY STABILIZED: 8.45 AC

IMPERVIOUS AREA: 3.24 AC (140,985 SF)

ALL WORK ON THIS PROJECT SHALL MARYLAND DEPARTMENT OF TRANSPOTATION STATE HIGHWAY ADMINISTRATION (MDOT SHA) "STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS" THERETO, AS INDICATED IN THE PROJECT DESCRIPTION OF THE INVITATION FOR BIDS BOOK: THE INVITATION FOR BIDS BOOK; THE ADMINISTRATION'S "BOOK OF STANDARDS FOR HIGHWAY AND

BENCHMARKS

SEE SHEET13 FOR BENCHMARK INFORMATION. BENCHMARKS FOR THIS PROJECT WERE SET BY PENNONI.

CONFORM TO THE LATEST APPROVED REVISIONS THEREOF OR ADDITIONS SPECIAL PROVISIONS INCLUDED IN THE INCIDENTAL STRUCTURES" AND THE LATEST ADOPTED MUTCD.

GP# G02017905

DWG NO: DD01A

ANNE ARUNDEL COUNTY

DEPARTMENT OF PUBLIC WORKS SCALE: 1" = 1.000"

97068 APRIL 5, 202

COVER SHEET

BROADNECK TRAIL CONSTRUCTION DOCUMENTS TAX MAP 32, 39, AND 40 ARNOLD, MD ZIP CODE 21012 3RD DISTRICT

Corre CHIEF ENGINEER

CALL "MISS UTILITY" AT LEAST 72

HOURS IN ADVANCE OF CONSTRUCTION AT

1-800-257-7777

DRAWN BY: PAI

CHECKED BY: PJS/JAR SHEET 1 of 137 PROJECT #: P504100 PROPOSAL #:


ANNE ARUNDEL COUNTY, MD NOVEMBER 2019

AS-BUILT CERTIFICATION

PLANS HAVE BEEN CONSTRUCTED IN ACCORDANCE WITH THE PLANS AND SPECIFICATION EXCEPT AS NOTED IN RED ON THE "AS BUILT DRAWINGS".

NAME (PRINTED) MARYLAND REGISTRATION # ADD STATE CONTRACT #

DESCRIPTION



GENERAL NOTES

- 1. THIS FIELD RUN BOUNDARY WAS PERFORMED BY PENNONI ASSOCIATES, INC. ON OR ABOUT MARCH, 2017.
- 2. FIELD RUN TOPOGRAPHY WAS PERFORMED BY PENNONI DURING MARCH-JUNE 2017 AND AUGUST-SEPTEMBER 2018, TOPOGRAPHIC INFORMATION HAS BEEN SUPPLEMENTED BY ANNE ARUNDEL COUNTY AND UTILITY COMPANY GIS INFORMATION.
- THE EXISTENCE OF VEGETATED OR TIDAL WETLANDS, AND WATERS OF THE U.S. HAS BEEN INVESTIGATED, AND IS SHOWN BASED ON A REPORT PREPARED BY STRAUGHAN ENVIRONMENTAL, DATED AUGUST 2017.
- THE SPECIMEN TREES SHOWN ON THE PLAN ARE FROM A FOREST STAND DELINEATION PREPARED BY STRAUGHAN ENVIRONMENTAL, DATED MAY 2017.
- EXISTING UTILITIES SHOWN ON THIS PLAN SET WERE DEVELOPED USING EXISTING RECORD DRAWINGS AND BASE FILES FROM THE UTILITY COMPANIES. FROM VISIBLE MARKINGS AND FEATURES WITHIN THE PROJECT LIMITS, FROM FIELD SURVEYS. AND FROM LIMITED TEST PITS. UTILITIES SHOWN ARE FOR INFORMATIONAL PURPOSES ONLY. THE UTILITY INFORMATION SHOWN MAY BE INNACURATE OR INCOMPLETE. CONTRACTOR IS RESPONSIBLE FOR VERIFYING ALL EXISTING UTILITIES WITHIN THE PROJECT LIMITS OF WORK TO HIS OWN SATISFACTION PRIOR TO THE START OF CONSTRUCTION, CONTRACTOR SHALL TAKE ALL NECESSARY PRECAUTIONS TO PROTECT EXISTING UTILITIES, SHALL AVOID IMPACTS TO UTILITIES, AND SHALL MAINTAIN UNINTERRUPTED UTILITY SERVICE. ANY DAMAGE INCURRED DUE TO CONTRACTOR'S OPERATIONS SHALL BE REPAIRED IMMEDIATELY AT NO COST TO ANNE ARUNDEL COUNTY IN COORDINATION WITH THE AFFECTED UTILITY COMPANIES.
- SEE SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- UTILITY RELOCATION WILL BE PERFORMED BY CONTRACTOR UNLESS NOTED OTHERWISE IN THE PLANS. THE CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATION OF HIS CONSTRUCTION WITH THE CONSTRUCTION OF OTHER CONTRACTORS (INCLUDING BUT NOT LIMITED TO BG&E, VERIZON, AND CABLE TV UTILITY). REFER TO PROJECT MANUAL GENERAL SPECIAL PROVISIONS.
- CONTRACTOR SHALL MAINTAIN COVER OF 30" OVER ALL ELECTRICAL LINES. WHERE FEASIBLE, AND IN COORDINATION WITH BGE AND THE COUNTY, BGE'S DETAIL FOR SHALLOW COVER PROTECTION UNDER SIDEWALKS SHALL BE UTILIZED TO REDUCE THE COVER TO NO LESS THAN 12".
- 9. THE CONTRACTOR SHALL CALL "MISS UTILITY" 1-800-257-7777 A MINIMUM OF 72 HOURS PRIOR TO BEGINNING ANY EXCAVATION.
- 10. IT SHALL BE DISTINCTLY UNDERSTOOD THAT FAILURE TO MENTION SPECIFICALLY ANY WORK WHICH WOULD NATURALLY BE REQUIRED TO COMPLETE THE PROJECT SHALL NOT RELIEVE THE CONTRACTOR OF HIS RESPONSIBILITY TO COMPLETE SUCH WORK.
- 11. THE CONTRACTOR SHALL NOTIFY THE ANNE ARUNDEL COUNTY DEPARTMENT OF PUBLIC WORKS (410) 222-4126, AT LEAST FOURTEEN (14) DAYS PRIOR TO BEGINNING CONSTRUCTION.
- 12. GRID COORDINATES ARE BASED ON THE MARYLAND STATE PLANE COORDINATE SYSTEM NAD 83/91. VERTICAL ELEVATIONS ARE BASED UPON NAVD 88.
- 13. THE CONTRACTOR SHALL ADJUST MANHOLES, WATER, METER VALVES, HAND BOXES, AND OTHER APPURTENANCES TO FINAL GRADE. THE COST OF PERFORMING THESE ACTIVITIES SHALL BE INCIDENTAL TO THE CONTRACT PRICE PAID FOR VARIOUS PAVEMENT ITEMS.
- 14. UNLESS OTHERWISE NOTED, PIPE ELEVATIONS REFER TO THE PIPE INVERT.
- 15. THE CONTRACTOR SHALL BE RESPONSIBLE FOR REPLACING ANY EXISTING LIGHT POLES, TRAFFIC BARRIER, SIGNS, ETC., DAMAGED OR REMOVED BY HIM DURING CONSTRUCTION.
- 16. IT SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR TO NOTIFY THE ENGINEER OF ANY DEVIATION TO THIS PLAN PRIOR TO ANY FIELD CHANGES BEING MADE. THE CONTRACTOR ASSUMES ALL RESPONSIBILITY FOR ANY FIELD CHANGES OR ADJUSTMENTS WITHOUT NOTIFYING THE ENGINEER.
- 17. ALL WORK SHALL COMPLY WITH THE APPLICABLE PROVISIONS OF THE "2011" MARYLAND STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL" ISSUED BY THE MARYLAND DEPARTMENT OF THE ENVIRONMENT AND AMENDMENTS BY THE ANNE ARUNDEL SOIL CONSERVATION DISTRICT. CONTAINED HEREIN AND THE 2017 STANDARD SPECIFICATIONS FOR CONSTRUCTION AND MATERIALS ISSUED BY THE MARYLAND DEPARTMENT OF TRANSPORTATION STATE HIGHWAY ADMINISTRATION.
- 18. THE DESIGN FOR THIS PROJECT INCORPORATES FACILITIES FOR THE HANDICAPPED IN COMPLIANCE WITH STATE AND FEDERAL LEGISLATION.
- 19. WHERE CURB AND GUTTER ENDS ARE EXPOSED, PROVIDE A NOSE DOWN SECTION AT 3:1 SLOPE.
- 20. MATERIAL REMOVED DURING CONSTRUCTION SHALL BECOME THE CONTRACTOR'S PROPERTY UNLESS OTHERWISE NOTED ON THE PLANS OR IN THE SPECIAL PROVISIONS.
- 21. STORM DRAIN AND UTILITY INSTALLATION IN EXISTING PAVEMENT SHALL BE IN ACCORDANCE WITH MD STD. 578.1
- 22. SUBGRADE DRAINS SHALL BE PLACED WHEN WET SUBGRADE IS ENCOUNTERED AND AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL USE CIRCULAR PIPE UNDERDRAIN OUTLET TO CONNECT ALL EXISTING AND PROPOSED SUBGRADE DRAIN AND PERFORATED CIRCULAR PIPE UNDERDRAIN TO PROPOSED INLETS.
- 23. ALL INVERT ELEVATIONS ARE APPROXIMATE. INVERT ELEVATIONS OF INLETS AND PIPES MAY BE MODIFIED AS DIRECTED BY THE ENGINEER TO MEET CONDITIONS ENCOUNTERED DURING INSTALLATION OF DRAINAGE STRUCTURES. ALL PIPES AND DITCHES SHALL BE CONSTRUCTED ON A UNIFORM GRADE BETWEEN INVERT ELEVATIONS NOTED ON THE PLANS, UNLESS INDICATED OTHERWISE ON THE PLANS OR DETAILS OR AS DIRECTED BY THE ENGINEER. THE LOCATION AND LENGTH OF PIPE SHALL BE VERIFIED BY THE CONTRACTOR BEFORE ORDERING.
- 24. ALL CONSTRUCTION SHALL BE DONE IN ACCORDANCE WITH THE LATEST EDITION OF THE STANDARD SPECIFICATIONS AND DETAILS FOR CONSTRUCTION OF ANNE ARUNDEL COUNTY DEPARTMENT OF PUBLIC WORKS, AND THE DETAILS, CONTAINED HEREIN.
- 25. CONTRACTOR MUST HAND DIG NEAR EXISTING UNDERGROUND UTILITIES WITH LESS THAN OR EQUAL TO 3.0 FEET CLEAR DISTANCE.
- 26. EXISTING OVERHEAD POWER LINES ARE IN THE VICINITY OF THE PROJECT. AT NO TIME WILL THE POWER BE PERMITTED TO BE SHUT OFF. AT ALL TIMES DURING CONSTRUCTION, THE CONTRACTOR SHALL COMPLY ABSOLUTELY WITH THE MARYLAND HIGH VOLTAGE ACT. IT IS THE CONTRACTOR'S OBLIGATION TO VERIFY THE EXISTING LOCATION OF THE POWER LINES IN THE FIELD AND TO MAINTAIN AND ENFORCE CLEARANCE REQUIREMENTS SPECIFIED IN THE ACT.
- 27. PROPOSED FENCING SHALL BE 4' HIGH BLACK VINYL COATED CHAIN LINK, EXCEPT WHERE NOTED, OR SPLIT RAIL FENCE, AS SHOWN ON THE PLANS. FENCE TO BE INSTALLED WITH MINIMAL CLEARING.
- 28. ALL SCALED DIMENSIONS ON THE DRAWINGS ARE APPROXIMATE. BEFORE PROCEEDING WITH ANY WORK, THE CONTRACTOR SHALL CAREFULLY CHECK AND VERIFY ALL DIMENSIONS AND QUANTITIES, AND SHALL IMMEDIATELY INFORM THE OWNER'S REPRESENTATIVE OF ANY DISCREPANCIES BETWEEN THE INFORMATION ON THE DRAWINGS AND THE ACTUAL CONDITIONS, REFRAINING FROM DOING ANY WORK IN SAID AREAS UNTIL GIVEN APPROVAL TO DO SO BY THE OWNER'S REPRESENTATIVE.
- 29. WHEREVER REFERENCES ARE MADE TO STANDARDS OR CODES IN ACCORDANCE WITH WHICH WORK IS TO BE PERFORMED OR TESTED. THE EDITION OR REVISION OF THE STANDARDS AND CODES CURRENT ON THE EFFECTIVE DATE OF THIS CONTRACT SHALL APPLY, UNLESS OTHERWISE EXPRESSLY SET FORTH.
- 30. IN CASE OF CONFLICT AMONG ANY REFERENCED STANDARDS OR CODES OR BETWEEN ANY REFERENCED STANDARDS AND CODES AND THE SPECIFICATIONS. THE MORE RESTRICTIVE STANDARD SHALL APPLY OR OWNER'S REPRESENTATIVE SHALL DETERMINE WHICH SHALL GOVERN.
- 31. DUE TO THE PROJECT'S LOCATION IN THE COUNTY RIGHT-OF-WAY, FOREST CONSERVATION IS NOT REQUIRED BASED ON SECTION 5-103 OF THE NATURAL RESOURCES ARTICLE OF THE STATE OF MARYLAND CODE. CLEARING FOR THIS PROJECT ON OFFSITE PARCELS IS LESS THAN 20,000 SF, SO FOREST CONSERVATION IS NOT REQUIRED FOR THIS OFFSITE WORK, REFORESTATION WITHIN THE COUNTY RIGHT-OF-WAY HAS BEEN PROVIDED WHERE APPROPRIATE.

- 32. ALL TREES SHALL BE PLANTED A MINIMUM OF 8' FROM THE EDGE OF THE TRAIL.
- 33. ACCESS TO ALL DRIVEWAYS BY RESIDENTS SHALL BE MAINTAINED THROUGHOUT CONSTRUCTION.
- 34. THE CONTRACTOR SHALL BE RESPONSIBLE FOR PREPARING SHOP DRAWINGS AND DESIGN CALCULATIONS FOR ANY WALLS THAT DIFFER FROM THE BASIS OF DESIGN SHOWN IN THESE DRAWINGS. SHOP DRAWINGS AND DESIGN CALCULATIONS SHALL INCLUDE ALL RELEVANT INFORMATION SUCH AS DESIGN CRITERIA, MATERIAL SPECIFICATIONS, AND FOUNDATIONS. A PROFESSIONAL ENGINEER LICENSED IN THE STATE OF MARYLAND WILL SIGN AND SEAL ALL DRAWINGS AND CALCULATIONS.
- 35. PROPOSED RETAINING WALLS SHALL BE ANCHOR DIAMOND PRO RETAINING WALL SYSTEM SEGMENTAL BLOCK OR APPROVED EQUAL WHERE WALLS ARE VISIBLE FROM THE ROAD. WHERE WALLS ARE NOT VISIBLE FROM THE ROAD GABION BASKETS SHALL BE USED. SEE PLANS FOR DETAILS. SUBSTITUTES WILL BE ACCEPTED FOR THESE WALLS. ACCEPTABLE SUBSTITUTES FOR THESE WALLS MUST HAVE AN ATTRACTIVE FINISH, BUT A WIDE RANGE OF STYLES AND SIZES WILL BE CONSIDERED FOR SUBSTITUTES. INCLUDING LARGE SEGMENTAL BLOCK UNITS LIKE REDIROCK ®, VERSA-LOK BRONCO ®, OR OTHERS. ALL PRODUCT DATA FOR ANY PROPOSED SUBSTITUTE SHALL BE SUBMITTED FOR APPROVAL WITH APPROPRIATE ENGINEERED PLANS AND DESIGN CALCULATIONS AS NOTED ABOVE.
- 36. SEGMENTAL BLOCK RETAINING WALLS SHALL HAVE AN ANTI-GRAFFITTI COATING APPLIED AT THE COMPLETION OF CONSTRUCTION. CONTRACTOR TO SUBMIT A PRODUCT FOR APPROVAL
- 37. THE INTENT OF THESE PLANS IS TO MEET EXISTING GRADES WHERE THE PROPOSED TRAIL CONNECTS TO THE EXISTING ROAD: NO ROAD GRADE MODIFICATIONS OR ROAD REPAVING ARE INCLUDED IN THIS SCOPE UNLESS SPECIFICALLY NOTED.
- 38. CONTRACTOR TO MAINTAIN MAXIMUM SIDE SLOPES OF 3:1, EXCEPT IN CUT AREAS WHERE A 2:1 SLOPE MAY BE UTILIZED AS NOTED ON PLANS. CONTRACTOR TO ADJUST GRADES AS NEEDED TO MEET EXISTING CONDITIONS, AND MAINTAIN ADA REQUIREMENTS. CONTRACTOR TO AVOID THE CREATION OF SUMPS EXCEPT WHERE NOTED ON PLAN FOR STORM DRAINAGE OR STORMWATER MANAGEMENT PURPOSES.
- 39. MAXIMUM CROSS SLOPE ON TRAIL SHALL BE 1.5%. MAXIMUM RUNNING (LONGITUDINAL SLOPE ON TRAIL SHALL BE 4.5%. THE TRAIL WILL NOT PASS THE ADA INSPECTION IF THE SLOPES EXCEED 5%.
- 40. CONTRACTOR SHALL VERIFY ALL EXISTING SITE CONDITIONS PRIOR TO BEGINNING WORK. HE SHALL VERIFY SIZE AND LOCATIONS OF ALL UNDERGROUND UTILITIES AND EXCAVATE TEST PITS AT PROPOSED TIE IN LOCATIONS. DISCREPANCIES SHALL BE REPORTED TO THE ENGINEER WELL IN ADVANCE OF CONSTRUCTION START, START OF CONSTRUCTION BY THE CONTRACTOR SHALL CONSTITUTE FULL ACCEPTANCE OF ALL SITE CONDITIONS BY THE CONTRACTOR
- 41. PRIOR TO START OF CONSTRUCTION CONTRACTOR SHALL REQUEST CONTROL, STAKE OUT, AND VERIFY LOCATIONS OF ALL IMPROVEMENTS AND UTILITY TIE IN LOCATIONS. CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY OF ANY DISCREPANCIES WELL IN ADVANCE OF START OF CONSTRUCTION.
- 42. SCALING OF THESE PLANS IS DISCOURAGED UNLESS DIRECTED BY THE ENGINEER. IN THE EVENT OF A DISCREPANCY BETWEEN THE SCALED AND THE FIGURED DIMENSIONS, THE FIGURED DIMENSIONS SHALL BE HELD.
- 43. STAGING AREAS: CONTRACTOR SHALL RESTORE STAGING AREAS TO THEIR CONDITION PRIOR TO CONSTRUCTION. ALL WOODCHIP MULCH SHALL BE REMOVED. A MINIMUM OF 2" OF TOPSOIL SHALL BE PLACED OVER VEGETATED AREAS AND A THICK STAND OF GRASS ESTABLISHED. ALL PAVEMENT SHALL BE RESTORED TO PRECONSTRUCITON CONDITIONS. ALL LANDSCAPE PLANT MATERIAL SHALL BE REPLACED. CONTRACTOR SHALL DOCUMENT PHOTOGRAPHICALLY THE CONDITION OF THE STAGING AREAS PRIOR TO CONSTRUCTION AND AGREE ON A RESTORATION PLAN WITH COUNTY.
- 44. ALL TRAIL CROSSINGS AT DRIVEWAYS SHALL HAVE A MAXIMUM CROSS SLOPE OF 2% FOR THE ENTIRE WIDTH OF THE TRAIL.
- 45. ALL PROPOSED SIDEWALKS SHALL HAVE A MINIMUM WIDTH OF 5 FEET AND A MAXIMUM CROSSSLOPE OF 2%. PROVIDE A LEVEL LANDING AREA (2% OR LESS) 5'X5' WHERE SIDEWALKS CONNECT TO TRAIL. WHERE SIDEWALK TRANSITIONS TO AN EXISTING SIDEWALK OF LESS THAN 5' IN WIDTH, TRANSITION SHALL OCCUR OVER A MINIMUM OF 5'.
- 46. ALL EXISTING TRAFFIC SIGNS AND OBSTACLES SHALL BE LOCATED A MINIMUM OF 3' FROM THE EDGE OF THE TRAIL.
- 47. FOR ALL MDOT SHA STANDARDS REFERRED TO ON THE PLANS, THE CONTRACTOR MUST GO TO THE BOOK OF STANDARDS WHICH WILL HAVE THE MOST CURRENT VERSION. THE BOOK OF STANDARDS CAN BE ACCESSED AT: HTTPS://APPS.ROADS.MARYLAND.GOV/BUSINESSWITHSHA/BIZSTDSSPECS/ DESMANUALSTDPUB/PUBLICATIONSONLINE/OHD/BOOKSTD/INDEX.ASP
- 48. A MODIFICATION (MODIFICATION # 15902) WAS GRANTED FOR THIS PROJECT ON MAY 7, 2019, FOR DISTURBANCES ASSOCIATED WITH STEEP SLOPES, STEEP SLOPE BUFFERS, AND STREAM BUFFERS.
- 49. CONTRACTOR SHALL BE AWARE OF, FAMILIAR WITH, AND HAVE COPIES ON SITE OF ANSI 117, UFAS, AND ANY OTHER REQUIRED LOCAL, STATE, OR FEDERAL ORDINANCES.

SEQUENCE OF CONSTRUCTION (CONTINUED FROM SHEET 1)

PHASE 4 - KIMWOOD DRIVE TO JONES STATION ROAD EAST

29.UPON APPROVAL OF INSPECTOR BEGIN CLEARING AND GRADING FOR THE INSTALLATION OF A STAGING AREA IMMEDIATELY EAST OF ROSSLARE DRIVE. STAGING AREA SHALL BE STABILIZED WITH 6" (MIN.) OF WOODCHIP MULCH, PREFERABLY FROM MATERIAL CLEARED AND CHIPPED ON SITE. (2 DAYS)

30.BEGIN CLEARING FOR THE INSTALLATION OF CULVERTS, STORM DRAINS, DRAINAGE STRUCTURES, AND WATER LINE EXTENSION. (2 DAYS) 31.INSTALL CULVERTS, STORM DRAINS, STORM STRUCTURES, WATER LINE EXTENSION, AND RIP RAP.

INSTALL INLET PROTECTION AS SHOWN ON PLANS. (1 WEEK) 32.UPON COMPLETION OF STORM DRAINAGE WORK, BEGIN CLEARING AND GRADING TO ESTABLISH

TRAIL SUBGRADE. AS SLOPES 3:1 AND GREATER ARE COMPLETED, TOPSOIL, SEED, AND PLACE PERMANENT SOIL STABILIZATION MATTING. COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. ROUGH GRADE SHOULDER WIDENING AREA ACROSS FROM RAINTREE ENTRANCE. MAINTAIN ACCESS TO EXISTING DRIVEWAYS THROUGHOUT CONSTRUCTION. (6 WEEKS)

CONSTRUCTED, BRING GRADE UP TO ESTABLISH TRAIL SUBGRADE, COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. (4 WFFKS) 34.WITH THE ESTABLISHMENT OF TRAIL SUBGRADE, BEING INSTALLING STONE BASE AND ASPHALT

33.CONCURRENT WITH STEP 32, CONSTRUCT RETAINING WALL I. AS WALLS IN FILL ARE

PAVING. COMPLETE ALL WORK AT INTERSECTIONS. STABILIZE DISTURBED AREAS WITH SEED AND STRAW, AND INSTALL SOIL STABILIZATION MATTING IN SWALES. (4 WEEKS) 35.COMPLETE CROSSINGS OF COLLEGE PARKWAY AT KIMWOOD DRIVE, LOCUST RIDGE LANE, AND RAINTREE DRIVE. ALL WORK WITHIN ROADWAY SHALL BE COMPLETED USING SAME DAY STABILIZATION MEASURES. COMPLETE ALL TRAFFIC SIGNAL WORK. (3 WEEKS)

36. ONCE PAYING HAS BEEN COMPLETED AND SITE PRELIMINARY STABILIZED. COMPLETE FINAL GRADING FOR THE INSTALLATION OF STORMWATER MEASURES AND INSTALL ALL STORMWATER FACILITIES. STORMWATER FACILITIES SHALL NOT BE INSTALLED UNTIL CONTRIBUTING DRAINAGE AREA IS 95% STABILIZED. IF INSPECTOR ALLOWS EARLIER INSTALLATION, PROTECT PERIMETER OF FACILITY WITH RSF, AND COVER WITH FILTER FABRIC UNTIL LANDSCAPING IS INSTALLED. (3 WEEKS)

37.INSTALL LANDSCAPING, FENCING, AND REFORESTATION. (2 WEEKS) 38.WITH COMPLETION OF WORK AND STABILIZATION OF SITE, CONTACT COUNTY INSPECTOR FOR FINAL INSPECTION. WITH APPROVAL OF INSPECTOR, REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES. (1 WEEK)

LIST OF ABBREVIATIONS

		<u>LIST OF AB</u>	BREVIAT	IONS
AATUR		ABANDONED ACCORDING TO UTILITY RECORDS	N/A -	NOT APPLICABLE
A.D.T.	_	AVERAGE DAILY TRAFFIC	N.I.C -	NOT IN CONTRACT
AHD		AHEAD	NO	NUMBER
BGE	<u> </u>	BALTIMORE GAS AND ELECTRIC COMPANY	N.S	NORMAL SECTION
BIT.		BITUMINOUS	O.C	ON CENTER
BK.	• • • • • • • • • • • • • • • • • • •	BACK	o/s -	OFFSET
B.M.	•	BENCH MARK	P.C	POINT OF CURVE
BW		BOTTOM OF WALL	P/C -	POINT OF CROWN
B/L	_	BASELINE	P.C.A	POINT OF COMPOUND CURVE
CATV		CABLE TELEVISION	P/G.E	PROFILE GRADE ELEVATION
C&G	•	CURB AND GUTTER	P.G.L	PROFILE GRADE LINE
C.I.P.		CAST IN PLACE (OR CURB INLET PROTECTION)	P./G.L	PROFILE GROUND LINE
C.I.P.	_	CORRUGATED METAL PIPE	Р.Н	PUNCH HOLE
C.S.P.	er forei G e rfore	CORRUGATED STEEL PIPE	P.I	POINT OF INTERSECTION
C.O.		CLEAN OUT	P.O.C	POINT ON CURVE
COMB.		COMBINATION	P.O.T	POINT ON TANGENT
сомм.	•	COMMUNICATION	P/R -	POINT OF ROTATION
CONSTR.		CONSTRUCTION	P.R.C	POINT OF REVERSE CURVATURE
DWG.		DRAWING	P.T	POINT OF TANGENT
Dc		DEGREE OF CURVE	PVC -	POINT OF VERTICAL CURVE (OR
Δ		DELTA (CENTRAL ANGLE), DEGREES	POLYVINYL C	
D.I.		DROP INLET	PVI -	POINT OF VERTICAL INTERSECTION
DIA.		DIAMETER	PVMT	PAVEMENT
D.S.		DESIGN SPEED	P.V.A	POINT OF VERTICAL TANGENCY
Б.б. Е		ELECTRIC	R -	RADIUS
EB		EASTBOUND	R.C.P	REINFORCED CONCRETE PIPE
EOI		END OF INFORMATION	REF	REFERENCE
EORI		END OF RECORD INFORMATION	R.S.E	REVERTIBLE SLOPE EASEMENT
ERCCP		ELLIPTICAL REINFORCED CEMENT CONCRETE PIPE	RT	RIGHT
		뭐지만 되는 사람들은 가장 하는 것이 되었다.	RTE	ROUTE
ES		END STRUCTURE	R/W -	RIGHT OF WAY
EW EXIC		ENDWALL OR EACH WAY	SAN	SANITARY
EX., EXIST		EXISTING	S.D	STORM DRAIN
F.O.	-	FIBER OPTIC	S/E -	SUPER ELEVATION
F.S.	=	FULL SUPER	S.H.A	STATE HIGHWAY ADMINISTRATION
GA.	-	GAUGE OR GAGE	SMH	SEWER MANHOLE
G.H.V.		GAS HOUSE CONNECTION	S.S.D	STOPPING SIGHT DISTANCE
G.V.		GAS VALVE	STA	STATION
HDWL		HEADWALL	STD	STANDARD
G.W.	•	HANDHOLE	STRUCT	STRUCTURE
H.P.	•	HIGH POINT		TELEPHONE
	•		TC -	TRAFFIC CONTROL
INV.	•	· INVERT	T.C.A	TEMPORARY CONSTRUCTION
L	. - 1	LENGTH	EASEMENT	
L.P.	-	LOW POINT (OR LIGHT POLE)	T.C.P	TRAFFIC CONTROL PLANS
L.S.	-	LEVEL SECTION	Т.Н	TEST HOLE
LT.	-	(1 LEFT) (1 - 1 시간 (1)) (1) (1) (1) (1) (1) (1) (TW -	TOP OF WALL
M.B.	•	MAIL BOX	TYP	TYPICAL
MD	•	MARYLAND	U.D	UNDERDRAIN PIPE
MDE	-	MARYLAND DEPARTMENT OF	WB -	WESTBOUND
		THE ENVIRONMENT	W.M	WATER METER
M.H.	-	MANHOLE	W.S	WRAPPED STEEL
			WILLS	WATERS OF THE LINITED STATES

PHASE IV -JONES STATION ROAD EAST TO PENINSULA FARM ROAD

39.UPON APPROVAL OF INSPECTOR BEGIN CLEARING AND GRADING FOR THE INSTALLATION OF A STAGING AREA IMMEDIATELY EAST OF JONES STATION ROAD (WEST). STAGING AREA SHALL BE STABILIZED WITH 6" (MIN.) OF WOODCHIP MULCH, PREFERABLY FROM MATERIAL CLEARED AND CHIPPED ON SITE. (2 DAYS)

40.BEGIN CLEARING FOR THE INSTALLATION OF STORM DRAINS AND DRAINAGE STRUCTURES. (2 DAYS) 41.INSTALL STORM DRAINS AND RIP RAP. INSTALL INLET PROTECTION AS SHOWN ON PLANS. (1

42.UPON COMPLETION OF STORM DRAINAGE WORK, BEGIN CLEARING AND GRADING TO ESTABLISH TRAIL SUBGRADE. COMPLETE WORK WITHIN CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. (5 WEEKS) 43.CONCURRENT WITH STEP 42, CONSTRUCT RETAINING WALL J, L, AND M. AS WALLS IN FILL ARE CONSTRUCTED, BRING GRADE UP TO ESTABLISH TRAIL SUBGRADE. COMPLETE WORK WITHIN

CRITICAL ROOT ZONES OF SPECIMEN TREES AS NOTED ON SPECIMEN TREE PRESERVATION PLANS. (4 WEEKS) 44.SAWCUT PAVEMENT AND CONSTRUCT ROAD IMPROVEMENTS ALONG COLLEGE PARKWAY EAST OF AACC. IMPROVEMENTS TO BE CONSTRUCTED USING SAME DAY STABILIZATION MEASURES. (6

45.WITH THE ESTABLISHMENT OF TRAIL SUBGRADE, BEING INSTALLING STONE BASE AND ASPHALT PAVING. COMPLETE ALL WORK AT INTERSECTIONS. STABILIZE DISTURBED AREAS WITH SEED AND

STRAW. (4 WEEKS) 46.ONCE PAVING HAS BEEN COMPLETED AND SITE PRELIMINARY STABILIZED, COMPLETE FINAL GRADING FOR THE INSTALLATION OF STORMWATER MEASURES AND INSTALL ALL STORMWATER FACILITIES. STORMWATER FACILITIES SHALL NT BE INSTALLED UNTIL CONTRIBUTING DRAINAGE AREA IS 95% STABILIZED. IF INSPECTOR ALLOWS EARLIER INSTALLATION, PROTECT PERIMETER OF FACILITY WITH RSF, AND COVER WITH FILTER FABRIC UNTIL LANDSCAPING IS INSTALLED. (2 WEEKS)

47.INSTALL LANDSCAPING FENCING, AND REFORESTATION. (2 WEEKS) 48.WITH COMPLETION OF WORK AND STABILIZATION OF SITE, CONTACT COUNTY INSPECTOR FOR FINAL INSPECTION. WITH APPROVAL OF INSPECTOR, REMOVE ALL REMAINING SEDIMENT CONTROL DEVICES. (1 WEEK)

SYMBOL LEGEND

PROPERTY LINE AND ———————————————————————————————————	
RIGHT-OF-WAY	PROPOSED 2' CONTOUR 122
EXISTING 2' CONTOUR 52	PROPOSED 10' CONTOUR 120
EXISTING 10' CONTOUR	PROPOSED SPOT ELEVATION 21 ⁵⁰
EXISTING TREE LINE EXISTING SOILS	PROPOSED SUPER SILT FENCE ———————————————————————————————————
EXIOTING SOILS	PROPOSED SILT FENCE SF SF
EXISTING ASPHALT ROADWAY	PROPOSED REINFORCED RSF RSF RSF RSF
	PROPOSED DIVERSION FENCE ———————————————————————————————————
EXISTING BUILDINGS	
V minus distinct dist	PROPOSED PIPE SLOPE DRAIN
EXISTING WATER	PROPOSED SOIL STABILIZATION
EXISTING SEWER S S S	MATTING MATTING
EXISTING OVERHEAD ELECTRIC	
EXISTING UNDERGROUND ELECTRIC —— UE	PROPOSED STANDARD INLET SIP
EXISTING STORM DRAIN	
EXISTING GAS C C C	PROPOSED CURB INLET
EXISTING STREAM ————————————————————————————————————	PROTECTION I SII J
EXISTING STREAM BUFFER SB SB	PROPOSED COMBINATION INLET PROTECTION COIP
EXISTING WETLANDS	Thoreon on the second of the s
	STABILIZED CONSTRUCTION
EXISTING WETLAND BUFFER WB	ENTRANCE 30S
EXISTING CRITICAL AREA LIMITS — CAB — — — —	
OSTONIE (SOUTH AND OSTONIE)	SPECIMEN TREE TO BE REMOVED 8976
SPECIMEN TREE AND CRITICAL ROOT ZONE (EXISTING DRAINAGE AREA
	EXISTING DRAINAGE AREA
	SPECIMEN TREE SIGNAGE
PROPOSED ASPHALT TRAIL	
PROPOSED CONCRETE TRAIL	HEAVY EQUIPMENT EXCLUSION ZONE
PROPOSED RETAINING WALL	HEAVY EQUIPMENT EXCLUSION ZONE
PROPOSED FENCE	TREE PROTECTION FENCE TPD
PROPOSED STORM DRAIN	DOOT DDI ININO
PROPOSED ROOFTOP DISCONNECT	ROOT PRUNING — — — — — —
AREA [::::::::::::::::::::::::::::::::::::	DID DAD
PROPOSED MICRO-BIORETENTION	RIP RAP
FACILITY	
PROPOSED GRASS SWALE	
	PROPOSED SHADE TREE (•)
PROPOSED BIOSWALE	
forest bornt	
PROPOSED INFILTRATION BERM	PROPOSED SHRUBS
PROPOSED LIMIT OF DISTURBANCELOD	PROPOSED EVERGREEN TREE
	PROPOSED EVERGICELY TILLE
PROPOSED STREET LIGHT	
PROPOSED POWER POLE	PROPOSED REFORESTATION
PROPOSED TRACEIO PARRIER	
PROPOSED TRAFFIC BARRIER	
SOILS CHART	
MAP SYMBOL NAME EROS	ION K FACTOR HYDRIC SLOPE (%) HYDROLOGIC GRO
	CEVERE 0.27 NO 2.EV

WATER VALVE

WATERS OF THE UNITED STATES


LENGTH OF VERTICAL CURVE

ROUP SEVERE 0.37 NO 2-5% Adelphia-Holmdel complex SLIGH1 NO 0-2% Annapolis loamy sand 0.17 **SLIGHT** 0.17 NO 2-5% Annapolis loamy sand SLIGH' 0.17 NO 5-10% Annapolis loamy sand MODERAT Annapolis fine sandy loam 0.24 NO 2-5% Annapolis fine sandy loam MODERAT 0.24 NO 5-10% AsE MODERAT 0.24 Annapolis fine sandy loam NO 15-25% 0.24 Annapolis fine sandy loam MODERAT NO 25-40% AuB MODERAT 0.24 Annapolis-Urban land complex NO 0-5% AuD MODERAT 0.24 NO 5-15% Annapolis-Urban land complex Collington-Wist complex CoB SLIGH' 0.17 NO. 2-5% SLIGHT 0.17 NO 5-10% Collington-Wist complex CpD Collington-Wist-Urban land complex NO 5-15% CRD Collington and Annapolis soils SLIGHT 0.17 NO 10-15% CSE SLIGHT 0.17 Collington, Wist, and Westphalia soils NO 15-25% DuB MODERAT Donlonton-Urban land complex 0.24 NO 0-5% DwB NO 0-5% Downer-Hammonton-Urban land complex DwD NO 5-15% Downer-Hammonton-Urban land complex Downer-Phalanx complex SLIGHT 0.1 NO 5-10% Downer-Phalanx complex SLIGHT 10-15% 0.1 NO 5-15% EuD Evesboro-Galestown-Urban land complex NO NO 5-10% Evesboro and Galestown soils MxB Mattapex-Butlertown complex SEVERE 0.43 NO 2-5% D Mattapex-Butlertown complex SEVERE 0.43 NO 5-10% SEVERE 0.43 0-5% Mattapex-Butlertown-Urban land complex NO SLIGHT 0.02 0-5% Patapsco-Fort Mott-Urban land complex NO SLIGHT 0.02 5-15% Patapsco-Fort Mott-Urban land complex NO **SLIGHT** 0.15 2-5% Sassafras fine sandy loam NO MODERAT 0.32 NO 2-5% Sassafras loam SLIGHT 0.15 NO 15-25% Sassafras and Croom soils Sassafras-Urban land complex MODERATE 0.24 NO 0-5% В Sassafras-Urban land complex **SLIGHT** 5-15% 0.15 NO SLIGHT 5-10% Tinton loamy sand 0.1 NO **SLIGHT** NO 5-10% Tinton-Urban land complex 0.1 MODERATE Udorthents, loamy, sulfidic substratum 0.28 NO 0-5% UxD Udorthents, loamy, sulfidic substratum MODERAT 0.28 NO 5-15% SEVERE 0.37 Widewater and Issue soils YES 0-2% C/D 0.37 SEVERE YES 0-2% B/D Zekiah and Issue soils

ANNE ARUNDEL COUNTY

DWG NO: DD02

PROFESSIONAL CERTIFICATION: I, JAMES, A RUFF, PE ___ CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY OR APPROVED BY ME AND THAT I AM A DULY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE # 21774 EXPIRATION DATE 11/10/2021





8890 McGaw Road, Suite 100

Columbia, MD 21045

T 410.997.8900 F 410.997.9282



CHIEF ENGINEER **APPROVAL**

APPROVED

PROJECT MANAGER

CHIEF, RIGHT OF WAY SERVICES

SCALE: AS SHOWN DRAWN BY: PAI CHECKED BY: PJS/JAR SHEET___3__ of __<u>137__</u> PROJECT #: P504100

PROPOSAL #:


DEPARTMENT OF PUBLIC WORKS


GP# G02017905

GENERAL NOTES, LEGEND, AND ABBREVIATIONS BROADNECK TRAIL – PHASE III CONSTRUCTION DOCUMENTS TAX MAP 32, 39, AND 40 ARNOLD, MD ZIP CODE 21012 3RD DISTRICT

ANNE ARUNDEL COUNTY, MD

NOVEMBER 2019





PLAN OF TYPICAL FENCE PANEL

SPLIT RAIL FENCE NOTES:

1. POSTS AND RAILS SHALL BE CCA PRESSURE TREATED, LOCUST, CEDAR, OR OTHER ROT RESISTANT WOOD, OR APPROVED ALTERNATE. 2. RAILS SHALL BE NAILED TO POSTS WITH GALANIZED NAILS.

PVC PRIVACY FENCE NOTES:

2. TERMINAL POSTS AND LINE POSTS SHALL BE 5"X5"X108" WITH A NEW ENGLAND POST CAP, AND

SHALL HAVE 10" FOOTING

DIAMETER, AND 36" FOOTING

5. PICKETS SHALL BE 7 X 6"

9. CONCRETE FOR FOOTINGS

10. PROVIDE A MOWING GAP

UNDER FENCE, MIN. 2", MAX. 4".

SHALL BE SHA MIX NO. 2.

3. TOP AND BOTTOM RAIL SHALL

TOUNGE AND GROOVE PICKETS. 6. POST SPACING SHALL BE 96". 7. FENCE COLOR SHALL BE WHITE. 8. FENCE MATERIAL SHALL BE PVC.


CONSTRUCTION.

BE 1-3/4" X 5-1/2".

1. SUBMIT PRODUCT INFORMATION AND SHOP DRAWINGS OF PRIVACY


FENCE FOR COUNTY AND HARTING FARM HOA APPROVAL PRIOR TO





PVC PRIVACY FENCE

NOT TO SCALE



RESIDENTIAL DRIVEWAY SECTION / SCALE: 1" = 5'

FOR ALL MOOT SHA STANDARDS REFERRED TO ON THE PLANS, THE CONTRACTOR MUST GO TO THE BOOK OF STANDARDS FOR HIGHWAY AND INCIDENTAL STRUCTURES WHICH WILL HAVE THE MOST CURRENT VERSION. THE BOOK OF STANDARDS CAN BE ACCESSED AT: HTTPS://ROADS.MARYLAND.GOV


THE FOLLOWING STANDARDS SHALL BE UTILIZED FOR THIS PROJECT:

TRAFFIC BARRIER: MD 605.03, MD 605.10, MD 605.21, MD 605.23, MD 605.31

DETECTABLE WARNING: MD 655.40


RAMPS: MD655.11, MD 655.12, MD 655.13, MD 655.21

SHA DETAIL NOTES




NOTE: CONCRETE TRAIL SHALL USE SHA MIX NO. 2 CONCRETE.










VII-25 of 66

NOTE: CURB SHALL USE SHA MIX NO. 2 CONCRETE.

2 STANDARD COMBINATION CURB & GUTTER 5 / NOT TO SCALE



1) MILL A 1' WIDE X 1-1/2" DEEP STRIP 2 SAW-CUT THROUGH FULL DEPTH PAVING

3 INSTALL SUB BASE GRAVEL AND BASIC PAVEMENT PER THE TYPICAL PAVEMENT SECTION. (4) PROVIDE 1½" TOP SURFACE COARSE (HMA SUPERPAVE 9.5 MM, PG64S-22 LEVEL 2)*

*NOTE: LONGITUDINAL JOINTS FOR THE TOP SURFACE COARSE MUST NOT COINCIDE WITH THE FULL-DEPTH SAW-CUT JOINT



1. 2' SHOULDERS WITH MAXIMIMUM

PROVIDED ON EACH SIDE OF THE

BELOW THE TRAIL: 3:1 (IN SPECIFIC

SITUATIONS ALONG THE PROJECT

2:1 SLOPES ARE UTILIZED. THESE HAVE BEEN NOTED ON THE PLAN.

3. MINIMUM SLOPE AWAY FROM

4. SEE PLAN VIEWS FOR SPECIFIC

5. CROSS SLOPE OF TRAIL SHALL

BE 1.5%. SEE PLAN VIEWS FOR


THE TRAIL: 2%

GRADING ALONG TRAIL.

DIRECTION OF SLOPE.

SLOPE OF 1:6 SLOPE SHALL BE

2. MAXIMUM SLOPE ABOVE OR




 WHERE THE CURB IS TO BE CONSTRUCTED AS PART OF AN ACCESSIBLE CURB RAMP, THE MARYLAND STATE HIGHWAY ADMINISTRATION STANDARD CURB RAMP DETAILS SHALL


CHIEF, RIGHT OF WAY SERVICES


PROPOSAL #:

NOSE DOWN CURB

5 NOT TO SCALE







TRAFFIC BARRIER W-BEAM WITH TIMBER BACK RAIL

MD 605.22 (MODIFIED)

PROP. NORMAL W-BEAM PANEL 12 GA. STEEL (SEE STD. MD 605.22)

ASPHALT TRAIL

LID/UTILITY

3,000 PSI CONCRETE, MIN. 6" THICK, SHA MIX NO. 2

2" X 12" PRESSURE TREATED SOUTHERN YELLOW PINE

PROP. WOOD OFFSET BLOCK (SEE STD. MD 605.23)

PROP. METAL POST

 2" X 12" TIMBER RAILING OPPOSITE THE W-BEAM PANEL SHALL CONSIST OF NO SPLICES. ALL JOINTS MUST BE AT METAL POSTS. MAXIMM LENGTH OF 2" X 12" SHALL BE 12:.

EACH TIMBER RAILING BOARD SHALL BE SECURED TO THE METAL POSTS WITH 2 EACH

3 \W-BEAM WITH TIMBER BACK RAIL DETAIL

3. BOLTS SHALL BE 3" LONG.

5 / NOT TO SCALE

SECTION

1. CONCRETE SHALL BE TROWELED SMOOTH AND BROOM 2. CONCRETE SHALL EXTEND A MINIMUM OF 12" FROM UTILITY

STRUCTURE AND ENCOMPASS THE FULL WIDTH OF THE 3. PRIOR TO INSTALLING CONCRETE, UTILITY STRUCTURE SHALL BE ADJUSTED SO THAT TOP MATCHES FINAL GRADE.

10 MANHOLE TRANSITION DETAIL 5 / NOT TO SCALE

DWG NO: DD03B

APRIL 5, 2021

97072

TYPICAL SECTIONS AND DETAILS

BROADNECK TRAIL - PHASE III

CONSTRUCTION DOCUMENTS


ARNOLD, MD ZIP CODE 21012 3RD DISTRICT

TAX MAP 32, 39, AND 40


ANNE ARUNDEL COUNTY, MD


NOVEMBER 2019


\PROJECTS\AACO\AACO1701-Broodneck Peninsula Phase III\DESIGN_PUBLISH\DD- CD SET\AACO1701-DD03B.dwg





T 410.997.8900 F 410.997.9282










































ALIGNMENT 'B' FROM BAY DALE

COURT TO COLLEGE PARKWAY GP# G02017905 DWG NO: DD05G PROFESSIONAL CERTIFICATION: I, JAMES. A RUFF, PE ... CERTIFY THAT THESE DOCUMENTS WERE PREPARED BY OR APPROVED BY ME AND THAT I AM A DULY ANNE ARUNDEL COUNTY LICENSED PROFESSIONAL ENGINEER UNDER THE LAWS OF THE STATE OF MARYLAND LICENSE # 21774 EXPIRATION DATE 11/10/2021 97087 DEPARTMENT OF PUBLIC WORKS APPROVED SCALE: 1" = 40' GEOMETRY PLAN DRAWN BY: PAI





210 EP 3+26.30 499948.2477 1460203.9004





PENNONI ASSOCIATES INC. 8890 McGaw Road, Suite 100 Columbia, MD 21045 T 410.997.8900 F 410.997.9282 CHECKED BY: PJS/JAR SHEET 20 of 137 PROJECT #: P504100 PROPOSAL #:


CONSTRUCTION DOCUMENTS
TAX MAP 32, 39, AND 40 ARNOLD, MD ZIP CODE 21012 3RD DISTRICT ANNE ARUNDEL COUNTY, MD NOVEMBER 2019











DWG NO: DD06C

APRIL 5, 2021

97091

TRAIL PROFILES

BROADNECK TRAIL - PHASE III


CONSTRUCTION DOCUMENTS


TAX MAP 32, 39, AND 40


ARNOLD, MD ZIP CODE 21012 3RD DISTRICT


ANNE ARUNDEL COUNTY, MD


NOVEMBER 2019


















GMENT D - ROSSLARE DR TO KIMWOOD RD
HORIZONTAL SCALE: 1" = 40'
VERTICAL SCALE: 1" = 4'



DPW No.:

