

SECTION 02951**CONTINGENT TEMPORARY ACCOMMODATION OF TRAFFIC GRADED
AGGREGATE, BITUMINOUS CONCRETE, CALCIUM CHLORIDE****02951.01 GENERAL****A. Description**

Contingent materials for temporary accommodation of traffic shall be furnished and placed only where, when, and in the amounts directed by the Engineer. The work shall include furnishing and placing graded aggregate, and/or bituminous concrete, and/or calcium chloride in accordance with the Contract Documents.

B. Related Work Included Elsewhere

Maintenance of traffic; Sections 01410 through 01460.

C. Quality Assurance

Quality assurance shall be as specified in Section 01470.01.

D. Submittals

Submittals shall be as specified in Section 01470.01.

02951.02 MATERIALS**A. Materials Furnished by the County**

The County will not furnish any materials for temporary accommodation of traffic.

B. Contractor's Options

None.

C. Detailed Material Requirements

Detailed material requirements shall be as specified in Section 01470.02.

02951.03 EXECUTION

Execution shall be as specified in Section 01470.03.

02951.04 METHOD OF MEASUREMENT

Measurement for furnishing and placing graded aggregate, and/or bituminous concrete, and/or calcium chloride for temporary accommodation of traffic will be made on the basis of the weight of material ordered by the Engineer.

02951.05 BASIS OF PAYMENT

A. General

1. Payment will be made at the bid or fixed prices stipulated in the Proposal. The payments will include furnishing all labor, tools, equipment, and materials necessary to complete the work as directed and accepted by the Engineer in accordance with the Contract Documents.
2. Payment will be made only for materials which are utilized at the direction of the Engineer beyond the areas disturbed by the Contractor, his subcontractors, or suppliers. No payment will be made for quantities in excess of those ordered by the Engineer.

B. Graded Aggregate

1. Payment for furnishing and placing graded aggregate for temporary accommodation of traffic will be made per ton. Payment will include maintaining the finished surface by grading and furnishing and placing such additional material as necessary, until permanent restoration is complete.
2. A delivery ticket system shall be provided for accurately determining the amount of material delivered to the work site. The tickets shall be serially numbered and show date of delivery, gross weight, tare weight, and net weight of the material and the number of the truck. One copy of the ticket shall be given to the Engineer.

C. Bituminous Concrete

1. Payment for furnishing and placing bituminous concrete for temporary accommodation of traffic will be made per ton. Payment will include maintaining the finished surface by grading and furnishing and placing such additional material as necessary, until permanent restoration is complete.
2. A delivery ticket system shall be provided for accurately determining the amount of material delivered to the work site. The tickets shall be serially numbered and show date of delivery, gross weight, tare weight, and net weight of the material and the number of the truck. One copy of the ticket shall be given to the Engineer.

D. Calcium Chloride

Payment for furnishing and placing calcium chloride for temporary accommodation of traffic will be made per ton.

END OF SECTION